# FLOOD INSURANCE STUDY

## FEDERAL EMERGENCY MANAGEMENT AGENCY

**VOLUME 3 OF 5**

# VENTURA COUNTY, CALIFORNIA

### AND INCORPORATED AREAS

| COMMUNITY NAME | COMMUNITY NUMBER |
|---|---|
| CAMARILLO, CITY OF | 065020 |
| FILLMORE, CITY OF | 060415 |
| MOORPARK, CITY OF | 060712 |
| OJAI, CITY OF | 060416 |
| OXNARD, CITY OF | 060417 |
| PORT HUENEME, CITY OF | 065051 |
| SAN BUENAVENTURA, CITY OF | 060419 |
| SANTA PAULA, CITY OF | 060420 |
| SIM VALLEY, CITY OF | 060421 |
| THOUSAND OAKS, CITY OF | 060422 |
| VENTURA COUNTY, UNINCORPORATED AREAS | 060413 |

FEMA

**PRELIMINARY**

**09/30/2016**

**REVISED:**

FLOOD INSURANCE STUDY NUMBER
06111CV003D

Version Number 2.3.3.3

# TABLE OF CONTENTS
**Volume 1**



Figures

Tables



**Volume 2**



Figures



Tables

**Volume 3**

Page



Tables

Page

Exhibits



**Volume 4**

Exhibits

**Volume 5**
Exhibits



**Published Separately**

Flood Insurance Rate Map (FIRM)

## Table 24: Floodway Data

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION ( FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/ SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 110 | 1,270 | 4,650 | 1.0 | 233.5 | 233.5 | 234.5 | 1.0 |
| B | 1,307 | 701 | 2,734 | 1.8 | 233.7 | 233.7 | 234.7 | 1.0 |
| C | 3,375 | 269 | 656 | 7.3 | 237.9 | 237.9 | 237.9 | 0.0 |
| D | 5,849 | 44 | 466 | 10.2 | 250.4 | 250.4 | 250.4 | 0.0 |
| E | 6,808 | 20 | 129 | 22.0 | 255.1 | 255.1 | 255.1 | 0.0 |
| F | 7,768 | 36 | 208 | 13.7 | 271.2 | 271.2 | 271.2 | 0.0 |
| G | 8,650 | 27 | 98 | 28.8 | 273.3 | 273.3 | 273.4 | 0.1 |
| H | 9,039 | 46 | 238 | 12.9 | 295.2 | 295.2 | 295.3 | 0.1 |
| I | 10,078 | 53 | 293 | 10.5 | 304.3 | 304.3 | 304.5 | 0.2 |
| J | 11,538 | 22 | 135 | 22.6 | 321.6 | 321.6 | 322.0 | 0.4 |
| K | 11,856 | 39 | 291 | 15.4 | 337.0 | 337.0 | 337.3 | 0.3 |
| L | 13,809 | 57 | 215 | 20.9 | 363.8 | 363.8 | 364.2 | 0.4 |
| M | 24,300 | 136 | 458 | 9.0 | 601.5 | 601.5 | 601.5 | 0.0 |
| N | 25,280 | 780 | 4,494 | 0.9 | 604.0 | 604.0 | 604.0 | 0.0 |
| O | 26,470 | 660 | 3,277 | 1.0 | 604.0 | 604.0 | 604.1 | 0.1 |
| P | 28,350 | 490 | 1,532 | 1.8 | 605.7 | 605.7 | 605.8 | 0.1 |
| Q | 30,030 | 340 | 405 | 4.0 | 612.7 | 612.7 | 612.8 | 0.1 |
| R | 31,855 | 260 | 274 | 6.0 | 624.6 | 624.6 | 624.6 | 0.0 |
| S | 33,150 | 270 | 680 | 1.8 | 643.3 | 643.3 | 643.8 | 0.5 |

[1]Feet above confluence with Conejo Creek

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 125 | 15 | 250 | 11.7 | 258.3 | 258.3 | 258.3 | 0.0 |
| B | 1,314 | 300 | 580 | 5.1 | 263.0 | 263.0 | 263.3 | 0.3 |
| C | 2,377 | 167 | 412 | 7.1 | 270.7 | 270.7 | 270.9 | 0.2 |
| D | 4,874 | 160 | 349 | 8.4 | 290.5 | 290.5 | 290.6 | 0.1 |
| E | 5,251 | 350 | 613 | 4.8 | 293.8 | 293.8 | 293.9 | 0.1 |
| F | 5,848 | 560 | 544 | 5.4 | 296.8 | 296.8 | 297.0 | 0.2 |
| G | 6,983 | 73 | 123 | 12.3 | 304.1 | 304.1 | 304.4 | 0.3 |
| H | 7,312 | 16 | 89 | 17.0 | 307.5 | 307.5 | 307.5 | 0.0 |
| I | 7,873 | 12 | 51 | 26.3 | 312.1 | 312.1 | 312.1 | 0.0 |
| J | 9,077 | 12 | 51 | 26.1 | 336.7 | 336.7 | 336.7 | 1.0 |
| K | 9,838 | 12 | 52 | 25.8 | 352.6 | 352.6 | 352.8 | 0.2 |
| L | 10,168 | 12 | 55 | 24.3 | 359.5 | 359.5 | 360.2 | 0.7 |
| M | 10,269 | 12 | 47 | 28.6 | 362.3 | 362.3 | 362.3 | 0.0 |
| N | 10,423 | 14 | 41 | 20.8 | 365.6 | 365.6 | 365.6 | 0.0 |
| O | 10,573 | 16 | 86 | 10.0 | 373.4 | 373.4 | 373.4 | 0.0 |
| P | 10,922 | 39 | 92 | 9.3 | 378.9 | 378.9 | 378.9 | 0.0 |

[1]Feet above confluence with Arroyo Santa Rosa

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 45,400 | 60 | 416 | 14.9 | 106.3 | 106.3 | 106.3 | 0.0 |
| B | 46,300 | 120 | 456 | 13.6 | 118.2 | 118.2 | 118.2 | 0.0 |
| C | 47,300 | 200 | 1,230 | 6.6 | 150.4 | 150.4 | 150.4 | 0.0 |
| D | 48,400 | 130 | 966 | 7.0 | 151.6 | 151.6 | 151.6 | 0.0 |

[1]Feet above confluence with Calleguas Creek

TABLE 24

FEDERAL EMERGENCY MANAGEMENT AGENCY

**VENTURA COUNTY, CALIFORNIA**

AND INCORPORATED AREAS

**FLOODWAY DATA**

**FLOODING SOURCE: BEARDSLEY WASH**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A – H* | | | | | | | | |
| I | 50,544 | 231 | 2,634 | 9.9 | 149.8 | 149.8 | 150.6 | 0.8 |
| J | 54,147 | 134 | 1,721 | 15.6 | 173.6 | 173.6 | 173.6 | 0.0 |
| K | 56,199 | 536 | 6,411 | 4.3 | 190.3 | 190.3 | 190.3 | 0.0 |
| L | 59,895 | 1,007 | 5,123 | 5.4 | 196.4 | 196.4 | 196.4 | 0.0 |
| M | 61,794 | 410 | 3,758 | 7.4 | 211.4 | 211.4 | 211.4 | 0.0 |
| N | 65,392 | 675 | 5,376 | 5.1 | 234.6 | 234.6 | 234.6 | 0.0 |
| O | 66,847 | 318 | 2,126 | 13.0 | 242.5 | 242.5 | 242.5 | 0.0 |
| P | 67,901 | 353 | 1,910 | 14.5 | 248.4 | 248.4 | 248.4 | 0.0 |
| Q | 70,113 | 371 | 2,205 | 12.5 | 260.5 | 260.5 | 260.5 | 0.0 |
| R | 74,041 | 519 | 2,997 | 8.6 | 280.9 | 280.9 | 280.9 | 0.0 |
| S | 77,593 | 833 | 3,829 | 6.6 | 305.5 | 305.5 | 305.5 | 0.0 |
| T | 80,643 | 484 | 3,405 | 7.4 | 325.4 | 325.4 | 325.4 | 0.0 |
| U | 88,341 | 230 | 2,372 | 10.2 | 377.0 | 377.0 | 377.0 | 0.0 |
| V | 90,092 | 260 | 2,197 | 8.7 | 384.5 | 384.5 | 384.5 | 0.0 |
| W | 93,860 | 144 | 1,685 | 11.4 | 418.6 | 418.6 | 418.6 | 0.0 |
| X | 95,831 | 173 | 1,250 | 15.2 | 433.0 | 433.0 | 433.0 | 0.0 |
| Y | 97,526 | 110 | 1,304 | 14.6 | 445.6 | 445.6 | 445.6 | 0.0 |
| Z | 99,696 | 167 | 1,772 | 10.7 | 457.3 | 457.3 | 457.7 | 0.5 |
| AA | 102,734 | 133 | 1,145 | 16.6 | 483.7 | 483.7 | 483.8 | 0.0 |
| AB | 107,078 | 232 | 1,459 | 13.1 | 512.3 | 512.3 | 512.5 | 0.2 |
| AC | 110,715 | 182 | 3,130 | 7.1 | 541.8 | 541.8 | 542.5 | 0.7 |
| AD | 115,040 | 255 | 2,725 | 7.4 | 555.1 | 555.1 | 555.5 | 0.3 |

[1]Feet above mouth at Pacific Ocean

*Data not available

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: CALLEGUAS CREEK / ARROYO LAS POSAS / ARROYO SIMI**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| AE | 120,336 | 490 | 6,785 | 3.0 | 588.4 | 588.4 | 588.4 | 0.0 |
| AF | 124,146 | 437 | 6,995 | 3.8 | 603.8 | 603.8 | 603.9 | 0.1 |
| AG | 127,543 | 978 | 4,548 | 3.8 | 615.4 | 615.4 | 615.4 | 0.0 |
| AH | 131,030 | 915 | 5,057 | 5.2 | 631.8 | 631.8 | 632.4 | 0.6 |
| AI | 131,880 | 671 | 3,757 | 7.1 | 635.7 | 635.7 | 636.7 | 1.0 |
| AJ | 132,000 | 245 | 1,749 | 15.2 | 637.7 | 637.7 | 638.0 | 0.3 |
| AK | 132,380 | 407 | 3,595 | 7.4 | 642.8 | 642.8 | 643.5 | 0.7 |
| AL | 132,930 | 408 | 3,769 | 7.0 | 644.6 | 644.6 | 645.6 | 1.0 |
| AM | 133,355 | 250 | 2,058 | 12.9 | 645.8 | 645.8 | 646.1 | 0.3 |
| AN | 133,705 | 204 | 1,641 | 16.1 | 649.8 | 649.8 | 649.8 | 0.0 |
| AO | 134,030 | 275 | 2,874 | 8.5 | 654.2 | 654.2 | 654.7 | 0.5 |
| AP | 134,980 | 529 | 3,047 | 8.0 | 657.6 | 657.6 | 658.0 | 0.4 |
| AQ | 136,300 | 484 | 3,566 | 6.9 | 663.4 | 663.4 | 664.4 | 1.0 |
| AR | 137,100 | 250 | 2,435 | 10.1 | 666.9 | 666.9 | 667.1 | 0.2 |
| AS | 137,500 | 250 | 2,592 | 9.5 | 668.7 | 668.7 | 669.0 | 0.3 |
| AT | 138,130 | 250 | 1,930 | 12.7 | 671.6 | 671.6 | 671.6 | 0.0 |
| AU | 138,780 | 299 | 2,907 | 8.4 | 676.8 | 676.8 | 677.8 | 1.0 |
| AV | 140,130 | 208 | 2,517 | 9.5 | 682.5 | 682.5 | 682.8 | 0.3 |
| AW | 150,185 | 200 | 1,671 | 11.1 | 789.1 | 789.1 | 789.1 | 0.0 |
| AX | 151,185 | 132 | 1,139 | 16.2 | 791.6 | 791.2 | 791.6 | 0.4 |
| AY | 152,190 | 137 | 1,237 | 13.0 | 805.4 | 805.4 | 802.6 | 0.0 |
| AZ | 153,385 | 167 | 1,181 | 13.6 | 810.5 | 810.5 | 810.5 | 0.0 |

[1]Feet above mouth at Pacific Ocean

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

# FLOODWAY DATA

**FLOODING SOURCE: CALLEGUAS CREEK / ARROYO LAS POSAS / ARROYO SIMI**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| BA | 154,535 | 108 | 1,044 | 17.7 | 827.0 | 827.0 | 827.0 | 0.0 |
| BB | 155,680 | 181 | 1,544 | 12.0 | 837.3 | 837.3 | 837.3 | 0.0 |
| BC | 156,670 | 182 | 1,397 | 13.2 | 844.2 | 844.2 | 844.2 | 0.0 |
| BD | 157,700 | 163 | 1,585 | 11.7 | 851.7 | 851.7 | 851.7 | 0.0 |
| BE | 158,795 | 135 | 1,128 | 16.4 | 858.0 | 858.0 | 858.0 | 0.0 |
| BF | 159,940 | 123 | 893 | 14.6 | 867.2 | 867.2 | 867.3 | 0.1 |
| BG | 160,960 | 172 | 1,139 | 11.4 | 875.9 | 875.9 | 876.4 | 0.5 |
| BH | 161,675 | 185 | 939 | 13.8 | 881.5 | 881.5 | 881.5 | 0.0 |
| BI | 162,390 | 134 | 1,203 | 10.8 | 888.9 | 888.9 | 888.9 | 0.0 |
| BJ | 163,615 | 300 | 2,169 | 6.0 | 894.8 | 894.8 | 895.2 | 0.4 |
| BK | 164,615 | 135 | 932 | 14.0 | 896.9 | 896.9 | 896.9 | 0.0 |
| BL | 165,625 | 110 | 1,189 | 10.9 | 904.9 | 904.9 | 904.9 | 0.0 |
| BM | 166,665 | 225 | 2, 191 | 4.5 | 908.8 | 908.8 | 909.0 | 0.2 |
| BN | 167,865 | 89 | 639 | 15.3 | 915.5 | 915.5 | 915.5 | 0.0 |
| BO | 168,960 | 108 | 682 | 14.4 | 928.9 | 928.9 | 928.9 | 0.0 |
| BP | 170,160 | 93 | 728 | 13.5 | 938.0 | 938.0 | 938.0 | 0.0 |
| BQ | 171,325 | 95 | 653 | 15.0 | 952.2 | 952.2 | 952.2 | 0.0 |
| BR | 172,395 | 95 | 962 | 10.2 | 962.9 | 962.9 | 963.1 | 0.2 |
| BS | 173,410 | 90 | 869 | 11.3 | 966.8 | 966.8 | 967.3 | 0.5 |
| BT | 174,395 | 233 | 513 | 20.3 | 976.2 | 976.2 | 976.2 | 0.0 |
| BU | 175,401 | 110 | 1,222 | 6.6 | 984.1 | 984.1 | 984.1 | 0.0 |
| BV | 176,412 | 137 | 1,197 | 6.7 | 985.8 | 985.8 | 985.8 | 0.0 |
| BW | 177,447 | 56 | 791 | 10.1 | 988.5 | 988.5 | 988.5 | 0.0 |
| BX | 178,100 | 54 | 578 | 13.0 | 988.5 | 988.5 | 988.5 | 0.0 |
| BY | 178,483 | 54 | 539 | 13.9 | 988.5 | 988.5 | 988.5 | 0.0 |
| BZ | 179,483 | 54 | 407 | 18.4 | 989.3 | 989.3 | 989.3 | 0.0 |

[1]Feet above mouth at Pacific Ocean

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| CA | 180,351 | 54 | 289 | 26.0 | 990.5 | 990.5 | 990.5 | 0.0 |
| CB | 181,081 | 142 | 505 | 13.9 | 998.9 | 998.9 | 999.2 | 0.3 |
| CC | 181,711 | 81 | 739 | 9.5 | 1,007.3 | 1,007.3 | 1,007.7 | 0.4 |
| CD | 182,612 | 194 | 1,240 | 5.6 | 1,013.1 | 1,013.1 | 1,013.9 | 0.8 |
| CE | 183,331 | 430 | 2,192 | 3.2 | 1,022.0 | 1,022.0 | 1,022.0 | 0.0 |
| CF | 183,897 | 327 | 2,203 | 3.2 | 1,029.9 | 1,029.9 | 1,030.9 | 1.0 |
| CG | 186,198 | 390 | 1,303 | 2.6 | 1,046.0 | 1,046.0 | 1,047.0 | 1.0 |
| CH | 187,087 | 367 | 2,044 | 1.6 | 1,058.1 | 1,058.1 | 1,058.6 | 0.5 |
| CI | 187,587 | 519 | 1,479 | 2.3 | 1,062.3 | 1,062.3 | 1,062.8 | 0.5 |
| CJ | 188,377 | 288 | 1,243 | 2.7 | 1,071.4 | 1,071.4 | 1,072.1 | 0.7 |
| CK | 188,740 | 150 | 845 | 4.0 | 1,076.1 | 1,076.1 | 1,076.8 | 0.7 |
| CL | 189,615 | 183 | 683 | 4.9 | 1,086.9 | 1,086.9 | 1,087.4 | 0.5 |
| CM | 189,935 | 326 | 748 | 4.5 | 1,090.8 | 1,090.8 | 1,090.8 | 0.0 |
| CN | 190,245 | 324 | 730 | 4.6 | 1,096.0 | 1,096.0 | 1,096.0 | 0.0 |
| CO | 190,925 | 47 | 253 | 13.3 | 1,108.5 | 1,108.5 | 1,108.5 | 0.0 |
| CP | 191,585 | 40 | 302 | 11.1 | 1,120.2 | 1,120.2 | 1,120.4 | 0.2 |

[1]Feet above mouth at Pacific Ocean

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: CALLEGUAS CREEK / ARROYO LAS POSAS / ARROYO SIMI**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 2,600 | 90 | 778 | 4.6 | 57.5 | 57.5 | 57.5 | 0.0 |
| B | 3,100 | 84 | 675 | 5.3 | 57.8 | 57.8 | 57.8 | 0.0 |
| C | 4,600 | 105 | 740 | 4.8 | 59.3 | 59.3 | 59.3 | 0.0 |
| D | 5,600 | 133 | 830 | 4.0 | 60.3 | 60.3 | 60.3 | 0.0 |
| E | 7,600 | 118 | 512 | 6.6 | 63.7 | 63.7 | 63.7 | 0.0 |
| F | 11,600 | 126 | 621 | 5.8 | 75.7 | 75.7 | 75.7 | 0.0 |
| G | 14,600 | 124 | 574 | 5.4 | 83.5 | 83.5 | 83.5 | 0.0 |
| H | 16,015 | 46 | 238 | 12.9 | 87.8 | 87.8 | 87.8 | 0.0 |

[1]Feet above confluence with Revolon Slough

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: CAMARILLO HILLS DRAIN**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 0 | 213 | 2,547 | 8.8 | 94.4 | 94.4 | 95.4 | 1.0 |
| B | 1,201 | 413 | 4,164 | 5.4 | 100.1 | 100.1 | 100.8 | 0.7 |
| C | 2,488 | 1,102 | 7,293 | 3.1 | 101.7 | 101.7 | 102.3 | 0.6 |
| D | 3,096 | 1,437 | 4,833 | 4.6 | 102.2 | 102.2 | 102.7 | 0.5 |
| E | 3,162 | 1,449 | 4,897 | 4.6 | 102.4 | 102.4 | 102.9 | 0.5 |
| F | 4,536 | 1,589 | 5,933 | 3.8 | 104.5 | 104.5 | 104.7 | 0.2 |
| G | 5,636 | 1,461 | 6,405 | 3.5 | 105.7 | 105.7 | 105.8 | 0.1 |
| H | 6,557 | 1,180 | 4,329 | 5.2 | 107.1 | 107.1 | 107.3 | 0.2 |
| I | 6,643 | 1,520 | 4,916 | 4.6 | 107.4 | 107.4 | 107.5 | 0.1 |
| J | 7,162 | 1,520 | 4,916 | 4.6 | 107.4 | 107.4 | 107.5 | 0.1 |
| K | 8,089 | 2,410 | 9,417 | 2.4 | 109.3 | 109.3 | 109.3 | 0.0 |
| L | 9,974 | 1,898 | 4,937 | 4.7 | 110.8 | 110.8 | 110.8 | 0.0 |
| M | 11,322 | 1,180 | 3,994 | 10.8 | 113.6 | 113.6 | 114.0 | 0.4 |
| N | 12,451 | 1,526 | 7,032 | 8.0 | 117.1 | 117.1 | 117.4 | 0.3 |
| O | 12,770 | 2,303 | 12,739 | 4.3 | 117.9 | 117.9 | 118.2 | 0.3 |
| P | 12,888 | 1,881 | 10,591 | 5.3 | 117.9 | 117.9 | 118.2 | 0.3 |
| Q | 14,580 | 1,070 | 8,404 | 4.2 | 118.0 | 118.0 | 118.8 | 0.8 |
| R | 14,769 | 323 | 3,234 | 7.2 | 118.7 | 118.7 | 118.9 | 0.2 |
| S | 16,729 | 276 | 2,974 | 7.0 | 120.7 | 120.7 | 121.0 | 0.3 |
| T | 17,033 | 870 | 6,865 | 4.4 | 121.1 | 121.1 | 121.8 | 0.7 |
| U | 19,073 | 561 | 3,973 | 6.6 | 122.1 | 122.1 | 122.6 | 0.5 |
| V | 21,501 | 258 | 2,474 | 9.4 | 126.7 | 126.7 | 127.4 | 0.7 |

[1]Feet above Limit of Floodway*

*Limit of Floodway is approximately 160 feet upstream of confluence with Calleguas Creek

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: CONEJO CREEK**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| W | 25,229 | 280 | 3,383 | 6.8 | 143.3 | 143.3 | 143.3 | 0.0 |
| X | 26,043 | 635 | 2,859 | 8.2 | 150.2 | 150.2 | 150.2 | 0.0 |
| Y | 28,698 | 204 | 1,750 | 7.1 | 161.5 | 161.5 | 161.7 | 0.2 |
| Z | 30,035 | 157 | 2,551 | 8.2 | 177.3 | 177.3 | 177.6 | 0.3 |
| AA | 30,825 | 842 | 4,462 | 4.7 | 180.1 | 180.1 | 180.2 | 0.1 |
| AB | 33,492 | 1,230 | 2,790 | 7.5 | 187.4 | 187.4 | 187.4 | 0.0 |
| AC | 35,519 | 1,111 | 2,547 | 8.2 | 193.3 | 193.3 | 193.3 | 0.0 |
| AD | 34,631 | 1,162 | 2,913 | 7.1 | 195.3 | 195.3 | 195.3 | 0.0 |
| AE | 36,077 | 513 | 2,849 | 7.3 | 204.5 | 204.5 | 204.7 | 0.2 |
| AF | 36,762 | 603 | 2,555 | 8.1 | 208.9 | 208.9 | 208.9 | 0.0 |
| AG | 37,602 | 592 | 2,677 | 8.7 | 213.0 | 213.0 | 213.4 | 0.4 |
| AH | 38,781 | 197 | 1,729 | 13.4 | 218.1 | 218.1 | 218.2 | 0.1 |
| AI | 39,989 | 1,272 | 4,664 | 5.0 | 228.3 | 228.3 | 228.5 | 0.2 |
| AJ | 40,664 | 797 | 2,870 | 8.1 | 230.9 | 230.9 | 230.9 | 0.2 |
| AK | 41,530 | 423 | 2,335 | 9.7 | 235.5 | 235.5 | 236.4 | 0.9 |
| AL | 42,811 | 352 | 2,035 | 11.1 | 240.8 | 240.8 | 241.3 | 0.5 |

[1]Feet above Limit of Floodway*

*Limit of Floodway is approximately 160 feet upstream of confluence with Calleguas Creek

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: CONEJO CREEK**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 730 | 80 | 265 | 9.0 | 688.1 | 688.1 | 688.1 | 0.0 |
| B | 1,480 | 60 | 250 | 12.3 | 699.6 | 699.6 | 699.6 | 0.0 |
| C | 2,055 | 40 | 140 | 10.9 | 706.6 | 706.6 | 706.6 | 0.0 |
| D | 10,340 | 30 | 60 | 9.3 | 885.0 | 885.0 | 885.0 | 0.0 |

[1]Feet above confluence with Stewart Canyon Creek

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: FOX CANYON STORM DRAIN**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 4,810 | 150 | 321 | 5.1 | 81.6 | 81.6 | 82.5 | 0.9 |
| B | 6,370 | 100 | 250 | 6.0 | 92.8 | 92.8 | 92.9 | 0.1 |
| C | 7,250 | 100 | 237 | 6.3 | 96.3 | 96.3 | 96.3 | 0.0 |
| D | 8,000 | 100 | 218 | 6.4 | 99.4 | 99.4 | 99.6 | 0.2 |
| E | 9,440 | 60 | 198 | 6.1 | 106.3 | 106.3 | 107.2 | 0.9 |
| F | 10,400 | 60 | 217 | 4.8 | 110.1 | 110.1 | 110.6 | 0.5 |

[1]Feet above confluence with Camarillo Hills Drain

TABLE 24

FEDERAL EMERGENCY MANAGEMENT AGENCY

**VENTURA COUNTY, CALIFORNIA**

AND INCORPORATED AREAS

**FLOODWAY DATA**

**FLOODING SOURCE: LAS POSAS ESTATES DRAIN**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 250 | 27 | 124 | 15.2 | 435.4 | 435.4 | 435.5 | 0.1 |
| B | 850 | 58 | 345 | 5.5 | 445.2 | 445.2 | 445.8 | 0.6 |
| C | 1,300 | 29 | 157 | 12.0 | 447.5 | 447.5 | 447.6 | 0.1 |
| D | 2,050 | 30 | 197 | 9.6 | 455.6 | 455.6 | 455.6 | 0.0 |
| E | 2,600 | 12 | 106 | 11.8 | 461.8 | 461.8 | 462.6 | 0.8 |
| F | 3,550 | 121 | 1,194 | 2.0 | 471.7 | 471.7 | 471.7 | 0.0 |
| G | 4,300 | 65 | 289 | 8.1 | 471.7 | 471.7 | 471.7 | 0.0 |
| H | 5,600 | 86 | 354 | 6.6 | 476.9 | 476.9 | 476.9 | 0.0 |

[1]Feet above confluence with Calleguas Creek

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: PEACH HILL WASH**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 2,510 | 24 | 240 | 36.4 | 463.2 | 463.2 | 463.2 | 0.0 |
| B | 3,150 | 24 | 200 | 41.6 | 469.2 | 469.2 | 469.2 | 0.0 |
| C | 4,600 | 20 | 190 | 45.3 | 501.7 | 501.7 | 501.7 | 0.0 |
| D | 5,500 | 20 | 190 | 45.6 | 524.4 | 524.4 | 524.4 | 0.0 |
| E | 6,100 | 20 | 180 | 46.6 | 539.4 | 539.4 | 539.4 | 0.0 |
| F | 7,450 | 70 | 530 | 16.1 | 585.2 | 585.2 | 585.2 | 0.0 |
| G | 8,030 | 90 | 560 | 15.7 | 604.4 | 604.4 | 604.4 | 0.0 |

[1]Feet above mouth at Pacific Ocean

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: POLE CREEK**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 3,000 | 600 | 4,133 | 9.9 | 660.5 | 660.5 | 661.5 | 1.0 |
| B | 4,180 | 763 | 6,416 | 6.4 | 671.1 | 671.1 | 671.8 | 0.7 |
| C | 5,000 | 700 | 3,740 | 11.0 | 674.3 | 674.3 | 674.7 | 0.4 |
| D | 6,000 | 448 | 3,051 | 13.4 | 682.8 | 682.8 | 682.8 | 0.0 |
| E | 7,040 | 285 | 3,519 | 11.7 | 694.4 | 694.4 | 694.4 | 0.0 |

[1]Feet above mouth at Pacific Ocean

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: PIRU CREEK**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 200 | 433[2] | 1,977 | 5.2 | 14.6 | 14.6 | 16.0 | 1.4 |
| B | 450 | 287[2] | 1,988 | 5.2 | 16.3 | 16.3 | 17.8 | 1.5 |
| C | 790 | 21[2] | 376 | 23.3 | 22.3 | 22.3 | 23.9 | 1.6 |
| D | 1,665 | 21[2] | 535 | 15.9 | 37.5 | 37.5 | 40.4 | 2.9 |
| E | 2,165 | 136[2] | 1,776 | 5.8 | 47.1 | 47.1 | 49.5 | 2.4 |
| F | 2,665 | 149[2] | 1,941 | 5.3 | 53.8 | 53.8 | 56.6 | 2.8 |
| G | 3,065 | 113[2] | 1,296 | 8.0 | 64.4 | 64.4 | 67.2 | 2.8 |
| H | 3,465 | 180[2] | 2,112 | 4.9 | 70.4 | 70.4 | 73.2 | 2.8 |

[1]Feet above Pacific Ocean

[2]This width extends beyond county limits

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: RINCON CREEK**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 1,550 | 590 | 2,360 | 8.6 | 326.8 | 326.8 | 326.8 | 0.0 |
| B | 4,440 | 219 | 1,563 | 12.7 | 348.2 | 348.2 | 348.2 | 0.0 |
| C | 6,230 | 350 | 1,934 | 10.3 | 368.0 | 368.0 | 368.0 | 0.0 |
| D | 7,590 | 393 | 1,853 | 10.7 | 380.2 | 380.2 | 380.3 | 0.1 |
| E | 10,320 | 420 | 1,754 | 11.3 | 406.2 | 406.2 | 406.2 | 0.0 |
| F | 13,090 | 410 | 1,777 | 10.2 | 437.4 | 437.4 | 437.9 | 0.5 |
| G | 16,000 | 224 | 1,420 | 12.8 | 468.0 | 468.0 | 468.0 | 0.0 |
| H | 20,670 | 124 | 1,050 | 17.3 | 513.2 | 513.2 | 513.2 | 0.0 |
| I | 21,790 | 130 | 2,132 | 8.5 | 530.1 | 530.1 | 530.2 | 0.1 |
| J | 25,795 | 116 | 1,116 | 13.3 | 576.4 | 576.4 | 577.1 | 0.7 |
| K | 27,020 | 176 | 1,290 | 10.9 | 590.5 | 590.5 | 590.5 | 0.0 |
| L | 28,000 | 260 | 1,028 | 13.8 | 600.5 | 600.5 | 600.5 | 0.0 |
| M | 29,140 | 238 | 2,005 | 7.0 | 615.4 | 615.4 | 615.4 | 0.0 |
| N | 30,840 | 372 | 1,172 | 11.9 | 630.0 | 630.0 | 630.0 | 0.0 |
| O | 31,890 | 143 | 852 | 14.1 | 643.0 | 643.0 | 643.0 | 0.0 |
| P | 32,850 | 280 | 1,032 | 10.8 | 654.8 | 654.8 | 655.8 | 1.0 |
| Q | 34,350 | 320 | 1,148 | 9.8 | 678.3 | 678.3 | 679.0 | 0.7 |
| R | 36,065 | 230 | 1,026 | 12.0 | 700.6 | 700.6 | 701.4 | 0.8 |
| S | 37,740 | 150 | 616 | 11.4 | 725.4 | 725.4 | 726.1 | 0.7 |
| T | 38,715 | 170 | 635 | 11.0 | 744.9 | 744.9 | 745.3 | 0.4 |
| U | 39,735 | 105 | 542 | 12.9 | 758.7 | 758.7 | 758.7 | 0.0 |
| V | 41,580 | 100 | 532 | 13.1 | 794.6 | 794.6 | 794.6 | 0.0 |

[1]Feet above confluence with Ventura River

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: SAN ANTONIO CREEK**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 1,860 | 1,895 | 10,561 | 8.3 | 13.7 | 13.7 | 13.7 | 0.0 |
| B | 4,000 | 1,092 | 6,353 | 13.9 | 18.2 | 18.2 | 18.5 | 0.3 |
| C | 5,500 | 4,320 | 24,269 | 6.6 | 23.7 | 23.7 | 24.4 | 0.7 |
| D | 7,380 | 3,701 | 20, 155 | 8.0 | 27.1 | 27.1 | 28.1 | 1.0 |
| E | 9,700 | 3,040 | 20,606 | 7.8 | 33.1 | 33.1 | 34.1 | 1.0 |
| F | 12,360 | 1,980 | 13,456 | 12.0 | 41.9 | 41.9 | 41.9 | 0.0 |
| G | 15,000 | 1,150 | 12,314 | 13.1 | 48.2 | 48.2 | 48.2 | 0.0 |
| H | 18,000 | 1,490 | 14,827 | 10.9 | 55.2 | 55.2 | 56.2 | 1.0 |
| I | 20,600 | 1,590 | 22,576 | 7.1 | 64.8 | 64.8 | 65.3 | 0.5 |
| J | 23,450 | 1,683 | 18,624 | 8.6 | 68.5 | 68.5 | 68.9 | 0.4 |
| K | 25,600 | 1,488 | 10,493 | 15.3 | 72.1 | 72.1 | 72.1 | 0.0 |
| L | 28,200 | 1,620 | 13,499 | 11.9 | 80.7 | 80.7 | 80.7 | 0.0 |
| M | 31,000 | 1,430 | 12,321 | 13.1 | 86.2 | 86.2 | 86.2 | 0.0 |
| N | 34,000 | 1,400 | 13,752 | 11.7 | 96.4 | 96.4 | 96.8 | 0.4 |
| O | 37,000 | 1,880 | 15,625 | 10.3 | 100.9 | 100.9 | 101.2 | 0.3 |
| P | 40,000 | 1,500 | 9,072 | 17.7 | 109.4 | 109.4 | 109.4 | 0.0 |
| Q | 43,000 | 1,190 | 8,612 | 18.7 | 117.2 | 117.2 | 117.2 | 0.0 |
| R | 45,520 | 1,700 | 14,504 | 11.1 | 125.2 | 125.2 | 125.2 | 0.0 |
| S | 48,500 | 1,390 | 10,369 | 15.5 | 129.3 | 129.3 | 130.0 | 0.7 |
| T | 51,500 | 1,396 | 11,808 | 13.6 | 143.6 | 143.6 | 143.6 | 0.0 |
| U | 54,900 | 1,123 | 12,514 | 12.9 | 162.1 | 162.1 | 162.1 | 0.0 |
| V | 58,870 | 1,290 | 8,968 | 18.0 | 180.7 | 180.7 | 181.1 | 0.3 |
| W | 62,000 | 1,730 | 9,832 | 16.4 | 189.0 | 189.0 | 189.0 | 0.0 |
| X | 65,000 | 970 | 14,759 | 10.9 | 198.1 | 198.1 | 198.2 | 0.1 |
| Y | 68,000 | 1,020 | 12,698 | 12.7 | 208.2 | 208.2 | 208.2 | 0.0 |
| Z | 71,000 | 1,185 | 9,283 | 17.3 | 219.7 | 219.7 | 219.7 | 0.0 |

[1]Feet above mouth at Pacific Ocean

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: SANTA CLARA RIVER**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| AA | 73,600 | 1,486 | 14,008 | 11.5 | 227.6 | 227.6 | 227.7 | 0.1 |
| AB | 77,000 | 1,600 | 14,567 | 11.1 | 242.0 | 242.0 | 242.8 | 0.8 |
| AC | 80,100 | 1,300 | 11,200 | 14.4 | 250.8 | 250.8 | 251.1 | 0.3 |
| AD | 83,140 | 979 | 9,143 | 17.6 | 260.4 | 260.4 | 260.4 | 0.0 |
| AE | 87,100 | 2,420 | 25,904 | 6.2 | 271.9 | 271.9 | 272.8 | 0.9 |
| AF | 90,000 | 2,280 | 16,985 | 9.2 | 281.7 | 281.7 | 281.7 | 0.0 |
| AG | 93,000 | 2,860 | 14,946 | 10.5 | 288.8 | 288.8 | 288.8 | 0.0 |
| AH | 97,000 | 2,510 | 15,437 | 10.2 | 300.4 | 300.4 | 300.8 | 0.4 |
| AI | 100,800 | 2,227 | 15,948 | 9.8 | 308.5 | 308.5 | 308.5 | 0.0 |
| AJ | 104,000 | 2,160 | 18,465 | 8.5 | 322.0 | 322.0 | 322.8 | 0.8 |
| AK | 106,900 | 2,840 | 12,784 | 12.3 | 333.0 | 333.0 | 333.1 | 0.1 |
| AL | 109,960 | 3,380 | 16,244 | 9.7 | 344.0 | 344.0 | 344.8 | 0.8 |
| AM | 112,850 | 3,150 | 15,842 | 9.9 | 354.2 | 354.2 | 355.3 | 1.1 |
| AN | 116,160 | 2,780 | 16,948 | 9.3 | 367.3 | 367.3 | 367.4 | 0.1 |
| AO | 119,730 | 2,120 | 15,694 | 10.0 | 383.3 | 383.3 | 384.3 | 1.0 |
| AP | 120,420 | 2,230 | 9,210 | 10.0 | 384.8 | 384.8 | 384.8 | 0.0 |
| AQ | 122,100 | 1,520 | 11,007 | 8.9 | 392.3 | 392.3 | 392.4 | 0.1 |
| AR | 123,950 | 1,280 | 13,159 | 7.5 | 401.6 | 401.6 | 401.6 | 0.0 |
| AS | 125,000 | 1,450 | 12,352 | 7.9 | 406.1 | 406.1 | 406.1 | 0.0 |
| AT | 126,650 | 1,800 | 9,922 | 9.9 | 414.0 | 414.0 | 414.4 | 0.4 |
| AU | 127,600 | 400 | 9,001 | 10.9 | 418.9 | 418.9 | 419.3 | 0.4 |
| AV | 129,080 | 1,782 | 13,451 | 7.3 | 426.3 | 426.3 | 426.3 | 0.0 |
| AW | 130,910 | 1,920 | 8,693 | 11.3 | 431.8 | 431.8 | 432.6 | 0.8 |
| AX | 137,140 | 2,370 | 9,942 | 9.9 | 464.6 | 464.6 | 465.5 | 0.9 |
| AY | 140,070 | 1,862[2] | 8,358 | 11.7 | 482.2 | 482.2 | 482.5 | 0.3 |
| AZ | 142,660 | 1,900 | 10,646 | 9.2 | 496.1 | 496.1 | 496.3 | 0.2 |

[1]Feet above mouth at Pacific Ocean

[2]Floodway width does not include width of high ground area

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: SANTA CLARA RIVER**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| BA | 145,370 | 1,698 | 8,018 | 12.2 | 511.4 | 511.4 | 511.4 | 0.0 |
| BB | 148,050 | 2,448 | 12,171 | 8.1 | 527.2 | 527.2 | 527.5 | 0.3 |
| BC | 150,700 | 1,770 | 9,022 | 10.2 | 542.4 | 542.4 | 542.8 | 0.4 |
| BD | 152,500 | 1,720 | 10,296 | 8.9 | 553.4 | 553.4 | 553.9 | 0.5 |
| BE | 155,400 | 2,550 | 13,094 | 7.0 | 567.3 | 567.3 | 567.3 | 0.0 |
| BF | 158,500 | 2,640 | 10,888 | 8.5 | 582.5 | 582.5 | 583.2 | 0.7 |
| BG | 161,250 | 2,150 | 11,851 | 7.8 | 599.0 | 599.0 | 599.1 | 0.1 |
| BH | 163,550 | 1,785 | 9,210 | 10.0 | 612.2 | 612.2 | 612.2 | 0.0 |
| BI | 165,670 | 1,950 | 11,021 | 8.3 | 625.5 | 625.5 | 625.5 | 0.0 |
| BJ | 168,700 | 2,160 | 11,520 | 8.0 | 640.0 | 640.0 | 640.0 | 0.0 |
| BK | 176,090 | 2,100 | 8,096 | 7.4 | 681.3 | 681.3 | 681.6 | 0.3 |
| BL | 178,650 | 1,840 | 7,751 | 7.7 | 698.1 | 698.1 | 698.1 | 0.0 |
| BM | 181,300 | 1,165 | 6,406 | 9.4 | 711.9 | 711.9 | 712.0 | 0.1 |
| BN | 184,140 | 525 | 5,051 | 11.9 | 729.9 | 729.9 | 729.9 | 0.0 |
| BO | 186,400 | 675 | 5,270 | 11.4 | 742.6 | 742.6 | 742.6 | 0.0 |
| BP | 189,450 | 1,020 | 7,006 | 8.6 | 758.7 | 758.7 | 758.7 | 0.0 |
| BQ | 192,500 | 1,275 | 6,442 | 9.3 | 774.8 | 774.8 | 774.8 | 0.0 |
| BR | 197,880 | 1,565 | 8,327 | 7.2 | 808.1 | 808.1 | 808.1 | 0.0 |
| BS | 203,200 | 1,575/ 1,075[2] | 7,341 | 8.2 | 829.1 | 829.1 | 829.1 | 0.0 |

[1]Feet above mouth at Pacific Ocean

[2]Width/width within study area

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: SANTA CLARA RIVER**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 1,000 | 849 | 6,297 | 11.6 | 12.6 | 12.6 | 12.6 | 0.0 |
| B | 3,000 | 1,120 | 10,674 | 6.8 | 17.7 | 17.7 | 18.3 | 0.6 |
| C | 5,000 | 1,700 | 16,309 | 4.5 | 21.2 | 21.2 | 21.5 | 0.3 |
| D | 7,130 | 3,230 | 15,353 | 4.8 | 22.5 | 22.5 | 22.9 | 0.4 |

[1]Feet above mouth at Pacific Ocean

TABLE 24

FEDERAL EMERGENCY MANAGEMENT AGENCY

**VENTURA COUNTY, CALIFORNIA**

AND INCORPORATED AREAS

**FLOODWAY DATA**

**FLOODING SOURCE: SANTA CLARA RIVER BREAKOUT**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 9,500 | * | 11,170 | 7.2 | 418.6 | 418.6 | 418.6 | 0.0 |
| B | 12,100 | * | 11,260 | 7.1 | 436.7 | 436.7 | 436.7 | 0.0 |
| C | 19,800 | 706 | 9,002 | 10.2 | 504.3 | 504.3 | 504.3 | 0.0 |
| D | 22,500 | 1,000 | 9,172 | 10.0 | 532.7 | 532.7 | 532.9 | 0.2 |
| E | 25,200 | 420 | 5,426 | 17.0 | 559.9 | 559.9 | 559.9 | 0.0 |
| F | 28,100 | 473 | 5,148 | 17.9 | 586.2 | 586.2 | 586.3 | 0.1 |
| G | 30,300 | 282 | 4,179 | 22.0 | 611.4 | 611.4 | 611.4 | 0.0 |

[1]Feet above confluence with Santa Clara River

*Data not available

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: SESPE CREEK**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 2,225 | 105 | 463 | 12.2 | 666.2 | 666.2 | 666.2 | 0.0 |
| B | 3,080 | 64 | 241 | 11.3 | 684.1 | 684.1 | 684.1 | 0.0 |
| C | 4,200 | 52 | 229 | 12.2 | 705.4 | 705.4 | 705.4 | 0.0 |

[1]Feet above confluence with San Antonio Creek

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

**FLOODWAY DATA**

**FLOODING SOURCE: STEWART CANYON CREEK**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 350 | 115 | 549 | 12.4 | 723.5 | 723.5 | 723.5 | 0.0 |
| B | 1,650 | 137 | 578 | 11.8 | 748.7 | 748.7 | 748.7 | 0.0 |
| C | 3,190 | 200 | 577 | 10.6 | 777.7 | 777.7 | 777.7 | 0.0 |
| D | 3,620 | 200 | 663 | 9.2 | 786.5 | 786.5 | 786.5 | 0.0 |
| E | 4,700 | 200 | 641 | 9.5 | 803.0 | 803.0 | 803.0 | 0.0 |
| F | 5,590 | 200 | 641 | 9.2 | 816.7 | 816.7 | 816.7 | 0.0 |
| G | 7,208 | * | * | * | 840.7 | * | * | * |
| H | 8,783 | * | * | * | 869.1 | * | * | * |

[1]Feet above confluence with San Antonio Creek

*Data not available

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: THATCHER CREEK**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| A | 1,540 | 1,621 | 11,256 | 6.9 | 17.2 | 17.2 | 17.2 | 0.0 |
| B | 2,570 | 1,279 | 6,557 | 11.9 | 20.7 | 20.7 | 20.7 | 0.0 |
| C | 3,700 | 986 | 8,080 | 9.7 | 29.0 | 29.0 | 29.1 | 0.1 |
| D | 5,500 | 608 | 6,017 | 13.0 | 40.7 | 40.7 | 41.1 | 0.4 |
| E | 7,500 | 840 | 9,209 | 8.5 | 49.8 | 49.8 | 49.8 | 0.0 |
| F | 9,500 | 683 | 4,969 | 15.7 | 65.5 | 65.5 | 65.5 | 0.0 |
| G | 11,500 | 1,150 | 5,657 | 13.8 | 78.9 | 78.9 | 78.9 | 0.0 |
| H | 13,500 | 464 | 4,307 | 17.6 | 97.8 | 97.8 | 97.8 | 0.0 |
| I | 15,450 | 450 | 3,933 | 19.3 | 118.1 | 118.1 | 118.1 | 0.0 |
| J | 17,224 | 600 | 7,978 | 9.5 | 134.4 | 134.4 | 134.6 | 0.2 |
| K | 19,150 | 556 | 4,842 | 15.8 | 149.1 | 149.1 | 149.1 | 0.0 |
| L | 21,050 | 335 | 3,774 | 20.1 | 161.2 | 161.2 | 161.3 | 0.1 |
| M | 23,250 | 1,000 | 6,064 | 12.2 | 175.8 | 175.8 | 175.8 | 0.0 |
| N | 25,350 | 465 | 4,273 | 16.4 | 191.1 | 191.1 | 191.1 | 0.0 |
| O | 27,600 | 510 | 4,379 | 16.0 | 206.3 | 206.3 | 206.3 | 0.0 |
| P | 29,750 | 343 | 3,611 | 19.4 | 223.9 | 223.9 | 223.9 | 0.0 |
| Q | 32,000 | 850 | 9,336 | 7.5 | 239.4 | 239.4 | 239.4 | 0.0 |
| R | 34,000 | 689 | 4,458 | 14.6 | 250.3 | 250.3 | 250.5 | 0.2 |
| S | 36,000 | 673 | 4,639 | 14.0 | 266.6 | 266.6 | 267.0 | 0.4 |
| T | 38,000 | 740 | 4,795 | 13.6 | 286.3 | 286.3 | 287.3 | 1.0 |
| U | 40,000 | 800 | 4,857 | 13.4 | 303.8 | 303.8 | 304.7 | 0.9 |
| V | 42,000 | 679 | 5,110 | 8.0 | 322.2 | 322.2 | 322.3 | 0.1 |
| W | 44,000 | 1,550 | 5,282 | 7.8 | 345.4 | 345.4 | 345.4 | 0.0 |
| X | 46,000 | 1,987 | 5,318 | 7.7 | 369.5 | 369.5 | 369.5 | 0.0 |
| Y | 48,000 | 809 | 4,044 | 9.9 | 397.7 | 397.7 | 398.5 | 0.8 |
| Z | 51,000 | 507 | 3,710 | 10.8 | 429.1 | 429.1 | 429.1 | 0.0 |

[1]Feet above Pacific Ocean

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: VENTURA RIVER**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| AA | 53,000 | 974 | 3,675 | 10.9 | 456.7 | 456.7 | 456.7 | 0.0 |
| AB | 55,000 | 1,097 | 3,625 | 11.0 | 482.2 | 482.2 | 482.6 | 0.4 |
| AC | 57,000 | 1,201 | 3,885 | 9.8 | 511.4 | 511.4 | 511.4 | 0.0 |
| AD | 59,000 | 771 | 3,175 | 12.0 | 543.4 | 543.4 | 543.4 | 0.0 |
| AE | 61,000 | 1,509 | 3,758 | 10.1 | 569.5 | 569.5 | 570.4 | 0.9 |
| AF | 63,000 | 1,049 | 3,607 | 10.5 | 599.1 | 599.1 | 599.3 | 0.2 |
| AG | 65,000 | 850 | 3,210 | 11.8 | 626.2 | 626.2 | 626.2 | 0.0 |
| AH | 67,000 | 1,760 | 3,520 | 10.8 | 657.9 | 657.9 | 657.9 | 0.0 |
| AI | 69,000 | 1,833 | 4,290 | 8.9 | 692.4 | 692.4 | 692.4 | 0.0 |
| AJ | 71,000 | 1,350 | 3,969 | 9.6 | 726.8 | 726.8 | 727.5 | 0.7 |
| AK | 73,000 | 935 | 3,155 | 11.6 | 759.2 | 759.2 | 759.6 | 0.4 |
| AL | 75,000 | 313 | 2,330 | 15.7 | 783.3 | 783.3 | 783.3 | 0.0 |
| AM | 77,000 | 428 | 2,528 | 13.8 | 809.8 | 809.8 | 809.8 | 0.0 |
| AN | 78,500 | 570 | 3,686 | 9.5 | 831.2 | 831.2 | 831.2 | 0.0 |
| AO | 80,500 | 480 | 2,270 | 15.4 | 878.0 | 878.0 | 878.0 | 0.0 |
| AP | 82,000 | 239 | 2,067 | 16.9 | 907.0 | 907.0 | 907.0 | 0.0 |
| AQ | 84,000 | 142 | 1,488 | 18.5 | 955.2 | 955.2 | 955.2 | 0.0 |

[1]Feet above Pacific Ocean

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

## FLOODWAY DATA

**FLOODING SOURCE: VENTURA RIVER**

| LOCATION | | FLOODWAY | | | 1% ANNUAL CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD88) | | | |
|---|---|---|---|---|---|---|---|---|
| CROSS SECTION | DISTANCE[1] | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET/SEC) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | INCREASE |
| S | 36,000 | 673 | 4,639 | 14.0 | 266.6 | 266.6 | 267.0 | 0.4 |
| T | 38,000 | 740 | 4,795 | 13.6 | 286.3 | 286.3 | 287.3 | 1.0 |
| U | 40,000 | 800 | 4,857 | 13.4 | 303.8 | 303.8 | 304.7 | 0.9 |

[1]Feet above mouth at Pacific Ocean

TABLE 24

**FEDERAL EMERGENCY MANAGEMENT AGENCY**

**VENTURA COUNTY, CALIFORNIA**

**AND INCORPORATED AREAS**

**FLOODWAY DATA**

**FLOODING SOURCE: VENTURA RIVER WITHOUT CONSIDERATION OF LEVEE**

### Table 25: Flood Hazard and Non-Encroachment Data for Selected Streams
### [Not Applicable to this Flood Risk Project]

## 6.4 Coastal Flood Hazard Mapping

Flood insurance zones and BFEs including the wave effects were identified on each transect based on the results from the onshore wave hazard analyses. Between transects, elevations were interpolated using topographic maps, land-use and land-cover data, and knowledge of coastal flood processes to determine the aerial extent of flooding. Sources for topographic data are shown in Table 23.

Zone VE is subdivided into elevation zones and BFEs are provided on the FIRM.

The limit of Zone VE shown on the FIRM is defined as the farthest inland extent of any of these criteria (determined for the 1% annual chance flood condition):

- The *primary frontal dune zone* is defined in 44 CFR Section 59.1 of the NFIP regulations. The primary frontal dune represents a continuous or nearly continuous mound or ridge of sand with relatively steep seaward and landward slopes that occur immediately landward and adjacent to the beach. The primary frontal dune zone is subject to erosion and overtopping from high tides and waves during major coastal storms. The inland limit of the primary frontal dune zone occurs at the point where there is a distinct change from a relatively steep slope to a relatively mild slope.

- The *wave runup zone* occurs where the (eroded) ground profile is 3.0 feet or more below the 1-percent annual chance TWL.

- The *wave overtopping splash zone* is the area landward of the crest of an overtopped barrier, in cases where the potential 1-percent annual chance TWL.

- The *breaking wave height zone* occurs where 3-foot or greater wave heights could occur (this is the area where the wave crest profile is 2.1 feet or more above the total stillwater elevation).

- The *high-velocity flow zone* is landward of the overtopping splash zone (or area on a sloping beach or other shore type), where the product of depth of flow times the flow velocity squared ($hv^2$) is greater than or equal to 200 $ft^3/sec^2$. This zone may only be used on the Pacific Coast.

The SFHA boundary indicates the limit of SFHAs shown on the FIRM as either "V" zones or "A" zones.

Table 26 indicates the coastal analyses used for floodplain mapping and the criteria used to determine the inland limit of the open-coast Zone VE and the SFHA boundary at each transect.

**Table 26: Summary of Coastal Transect Mapping Considerations**

| Coastal Transect | Primary Frontal Dune (PFD) Identified | Wave Runup Analysis | Wave Height Analysis | Zone VE Limit | SFHA Boundary |
|---|---|---|---|---|---|
| | | Zone Designation and BFE (ft NAVD88) | Zone Designation and BFE (ft NAVD88) | | |
| 1 | | VE 13 | N/A | Runup | Overtopping |
| 2 | | VE 33 | N/A | Runup | Overtopping |
| 3 | | VE 15 | N/A | Runup | Runup |
| 4 | | VE 16 | N/A | Runup | Runup |
| 5 | | VE 29 | N/A | Runup | Overtopping |
| 6 | | VE 20 | N/A | Runup | Overtopping |
| 7 | | VE 33 | N/A | Runup | Overtopping |
| 8 | | VE 20, 34 | N/A | Runup | Overtopping |
| 9 | | VE 21, 30 | N/A | Runup | Overtopping |
| 10 | | VE 19, 26 | N/A | Runup | Overtopping |
| 11 | | VE 23, 37 | N/A | Runup | Overtopping |
| 12 | | VE 19, 26 | N/A | Runup | Overtopping |
| 13 | | VE 17, 21 | N/A | Runup | Overtopping |
| 14 | | VE 17, 26 | N/A | Runup | Overtopping |
| 15 | | VE 21 | N/A | Runup | Overtopping |
| 16 | | VE 21, 24 | N/A | Runup | Overtopping |
| 17 | | VE 25 | N/A | Runup | Overtopping |
| 18 | | VE 29 | N/A | Runup | Overtopping |
| 19 | | VE 18, 28 | N/A | Runup | Overtopping |
| 20 | | VE 20, 27 | N/A | Runup | Overtopping |
| 21 | | VE 19 | N/A | Runup | Overtopping |
| 22 | | VE 19 | N/A | Runup | Overtopping |
| 23 | | VE 18 | N/A | Runup | Overtopping |
| 24 | | VE 20 | N/A | Runup | Overtopping |
| 25 | | VE 19 | N/A | Runup | Overtopping |
| 26 | | VE 21 | N/A | Runup | Overtopping |
| 27 | | VE 26 | N/A | Runup | Overtopping |
| 28 | | VE 24 | N/A | Runup | Overtopping |

**Table 26: Summary of Coastal Transect Mapping Considerations, continued**

| Coastal Transect | Primary Frontal Dune (PFD) Identified | Wave Runup Analysis | Wave Height Analysis | Zone VE Limit | SFHA Boundary |
|---|---|---|---|---|---|
| | | Zone Designation and BFE (ft NAVD88) | Zone Designation and BFE (ft NAVD88) | | |
| 29 | | VE 16, 25 | N/A | Runup | Overtopping |
| 30 | | VE 17, 22 | N/A | Runup | Overtopping |
| 31 | | VE 11 | N/A | Runup | Runup |
| 32 | | VE 11, 16-18, 22 | N/A | Runup | Runup |
| 33 | | VE 11, 17-18 | N/A | Runup | Runup |
| 34 | | VE 11, 17 | N/A | Runup | Overtopping |
| 35 | | VE 16<br>AE 16 | N/A | Runup | Overtopping |
| 36 | | VE 22 | N/A | Runup | Overtopping |
| 37 | | VE 18 | N/A | Runup | Runup |
| 38 | | VE 19 | N/A | Runup | Runup |
| 39 | | VE 16 | N/A | Runup | Overtopping |
| 40 | | VE 18 | N/A | Runup | Overtopping |
| 41 | | VE 18 | N/A | Runup | Overtopping |
| 42 | | VE 14 | N/A | Runup | Overtopping |
| 43 | | VE 9, 14 | N/A | Runup | Runup |
| 44 | | VE 20<br>AE 20 | N/A | Runup | Overtopping |
| 45 | | VE 19 | N/A | Runup | Runup |
| 46 | | VE 19 | N/A | Runup | Runup |
| 47 | | VE 20 | N/A | Runup | Runup |
| 48 | | VE 21 | N/A | Runup | Overtopping |
| 49 | | VE 20 | N/A | Runup | Overtopping |
| 50 | | VE 21 | N/A | Runup | Runup |
| 51 | | VE 18 | N/A | Runup | Runup |
| 52 | | VE 17 | N/A | Runup | Overtopping |
| 53 | | VE 11 | N/A | Runup | Overtopping |
| 54 | | VE 22 | N/A | Runup | Overtopping |
| 55 | | VE 24 | N/A | Runup | Overtopping |
| 56 | | VE 18 | N/A | Runup | Overtopping |

**Table 26: Summary of Coastal Transect Mapping Considerations, continued**

| Coastal Transect | Primary Frontal Dune (PFD) Identified | Wave Runup Analysis | Wave Height Analysis | Zone VE Limit | SFHA Boundary |
|---|---|---|---|---|---|
| | | Zone Designation and BFE (ft NAVD88) | Zone Designation and BFE (ft NAVD88) | | |
| 57 | | VE 14 – 15 | N/A | Runup | Overtopping |
| 58 | | VE 14 – 15 | N/A | Runup | Overtopping |
| 59 | | VE 15 | N/A | Runup | Runup |
| 60 | | VE 14 | N/A | Runup | Runup |
| 61 | | VE 22 | N/A | Runup | Overtopping |
| 62 | | VE 18 | N/A | Runup | Runup |
| 63 | | VE 16 | N/A | Runup | Overtopping |
| 64 | | VE 15<br>AE 8 | N/A | Runup | Overtopping |
| 65 | | VE 11, 16<br>AE 8 | N/A | Runup | Overtopping |
| 66 | | VE 17<br>AE 8 | N/A | Runup | Overtopping |
| 67 | | VE 18<br>AE 8 | N/A | Runup | Overtopping |
| 68 | ✓ | VE 19<br>AE 8 | N/A | PFD | PFD |
| 69 | | VE 15<br>AE 8 | N/A | Runup | Overtopping |
| 70 | | VE 16 | N/A | Runup | Runup |
| 71 | | VE 14, 20<br>AE 8 | N/A | Runup | Overtopping |
| 72 | | VE 15, 20 | N/A | Runup | Overtopping |
| 73 | | VE 18 | N/A | Runup | Overtopping |
| 74 | | VE 24 | N/A | Runup | Overtopping |
| 75 | | VE 13, 19<br>AE 8 | N/A | Runup | Overtopping |
| 76 | | VE 19, 26 | N/A | Runup | Overtopping |
| 77 | | VE 12, 17<br>AE 8 | N/A | Runup | Overtopping |
| 78 | | VE 22<br>AO 1 | N/A | Runup | Overtopping |

**Table 26: Summary of Coastal Transect Mapping Considerations, continued**

| Coastal Transect | Primary Frontal Dune (PFD) Identified | Wave Runup Analysis | Wave Height Analysis | Zone VE Limit | SFHA Boundary |
|---|---|---|---|---|---|
| | | Zone Designation and BFE (ft NAVD88) | Zone Designation and BFE (ft NAVD88) | | |
| 79 | | VE 22 | N/A | Runup | Overtopping |
| 80 | | VE 35 | N/A | Runup | Overtopping |
| 81 | | VE 18, 26 | N/A | Runup | Overtopping |
| 82 | | VE 20 | N/A | Runup | Overtopping |
| 83 | | VE 18, 22 | N/A | Runup | Overtopping |
| 84 | | VE 28 | N/A | Runup | Runup |
| 85 | | VE 20 | N/A | Runup | Runup |
| 86 | | VE 20 | N/A | Runup | Runup |
| 87 | | VE 18 | N/A | Runup | Runup |
| 88 | | VE 20, 34 | N/A | Runup | Overtopping |
| 89 | | VE 20 | N/A | Runup | Overtopping |
| 90 | | VE 19 | N/A | Runup | Runup |

## 6.5 FIRM Revisions

This FIS Report and the FIRM are based on the most up-to-date information available to FEMA at the time of its publication; however, flood hazard conditions change over time. Communities or private parties may request flood map revisions at any time. Certain types of requests require submission of supporting data. FEMA may also initiate a revision. Revisions may take several forms, including Letters of Map Amendment (LOMAs), Letters of Map Revision Based on Fill (LOMR-Fs), Letters of Map Revision (LOMRs) (referred to collectively as Letters of Map Change (LOMCs)), Physical Map Revisions (PMRs), and FEMA-contracted restudies. These types of revisions are further described below. Some of these types of revisions do not result in the republishing of the FIS Report. To assure that any user is aware of all revisions, it is advisable to contact the community repository of flood-hazard data (shown in Table 31, "Map Repositories").

### 6.5.1 Letters of Map Amendment

A LOMA is an official revision by letter to an effective NFIP map. A LOMA results from an administrative process that involves the review of scientific or technical data submitted by the owner or lessee of property who believes the property has incorrectly been included in a designated SFHA. A LOMA amends the currently effective FEMA map and establishes that a specific property is not located in a SFHA. A LOMA cannot be issued for properties located on the PFD (primary frontal dune).

To obtain an application for a LOMA, visit www.fema.gov/floodplain-management/letter-map-amendment-loma and download the form "MT-1 Application Forms and Instructions for Conditional and Final Letters of Map Amendment and Letters of Map Revision Based on Fill". Visit the "Flood Map-Related Fees" section to determine the cost, if any, of applying for a LOMA.

FEMA offers a tutorial on how to apply for a LOMA. The LOMA Tutorial Series can be accessed at www.fema.gov/online-tutorials.

For more information about how to apply for a LOMA, call the FEMA Map Information eXchange; toll free, at 1-877-FEMA MAP (1-877-336-2627).

### 6.5.2 Letters of Map Revision Based on Fill

A LOMR-F is an official revision by letter to an effective NFIP map. A LOMR-F states FEMA's determination concerning whether a structure or parcel has been elevated on fill above the base flood elevation and is, therefore, excluded from the SFHA.

Information about obtaining an application for a LOMR-F can be obtained in the same manner as that for a LOMA, by visiting www.fema.gov/floodplain-management/letter-map-amendment-loma for the "MT-1 Application Forms and Instructions for Conditional and Final Letters of Map Amendment and Letters of Map Revision Based on Fill" or by calling the FEMA Map Information eXchange, toll free, at 1-877-FEMA MAP (1-877-336-2627). Fees for applying for a LOMR-F, if any, are listed in the "Flood Map-Related Fees" section.

A tutorial for LOMR-F is available at www.fema.gov/online-tutorials.

### 6.5.3 Letters of Map Revision

A LOMR is an official revision to the currently effective FEMA map. It is used to change flood zones, floodplain and floodway delineations, flood elevations and planimetric features. All requests for LOMRs should be made to FEMA through the chief executive officer of the community, since it is the community that must adopt any changes and revisions to the map. If the request for a LOMR is not submitted through the chief executive officer of the community, evidence must be submitted that the community has been notified of the request.

To obtain an application for a LOMR, visit www.fema.gov/national-flood-insurance-program-flood-hazard-mapping/mt-2-application-forms-and-instructions and download the form "MT-2 Application Forms and Instructions for Conditional Letters of Map Revision and Letters of Map Revision". Visit the "Flood Map-Related Fees" section to determine the cost of applying for a LOMR. For more information about how to apply for a LOMR, call the FEMA Map Information eXchange; toll free, at 1-877-FEMA MAP (1-877-336-2627) to speak to a Map Specialist.

Previously issued mappable LOMCs (including LOMRs) that have been incorporated into the Ventura County FIRM are listed in Table 27. Please note that this table only includes LOMCs that have been issued on the FIRM panels updated by this map revision. For all other areas within this county, users should be aware that revisions to the FIS Report made by prior LOMRs may not be reflected herein and users will need to continue to use the previously issued LOMRs to obtain the most current data.

**Table 27: Incorporated Letters of Map Change**

| Case Number | Effective Date | Flooding Source | FIRM Panel(s) |
|---|---|---|---|
| 10-09-0815P | 01-21-2010 | Santa Clara River | 06111C0901F<br>06111C0902F<br>06111C0903F<br>06111C0904F<br>06111C0910E |

### 6.5.4 Physical Map Revisions

Physical Map Revisions (PMRs) are an official republication of a community's NFIP map to effect changes to base flood elevations, floodplain boundary delineations, regulatory floodways and planimetric features. These changes typically occur as a result of structural works or improvements, annexations resulting in additional flood hazard areas or correction to base flood elevations or SFHAs.

The community's chief executive officer must submit scientific and technical data to FEMA to support the request for a PMR. The data will be analyzed and the map will be revised if warranted. The community is provided with copies of the revised information and is afforded a review period. When the base flood elevations are changed, a 90-day appeal period is provided. A 6-month adoption period for formal approval of the revised map(s) is also provided.

For more information about the PMR process, please visit www.fema.gov and visit the "Flood Map Revision Processes" section.

### 6.5.5 Contracted Restudies

The NFIP provides for a periodic review and restudy of flood hazards within a given community. FEMA accomplishes this through a national watershed-based mapping needs assessment strategy, known as the Coordinated Needs Management Strategy (CNMS). The CNMS is used by FEMA to assign priorities and allocate funding for new flood hazard analyses used to update the FIS Report and FIRM. The goal of CNMS is to define the validity of the engineering study data within a mapped inventory. The CNMS is used to track the assessment process, document engineering gaps and their resolution, and aid in prioritization for using flood risk as a key factor for areas identified for flood map updates. Visit www.fema.gov to learn more about the CNMS or contact the FEMA Regional Office listed in Section 8 of this FIS Report.

### 6.5.6 Community Map History

The current FIRM presents flooding information for the entire geographic area of Ventura County. Previously, separate FIRMs, Flood Hazard Boundary Maps (FHBMs) and/or Flood Boundary and Floodway Maps (FBFMs) may have been prepared for the incorporated communities and the unincorporated areas in the county that had identified SFHAs. Current and historical data relating to the maps prepared for the project area are presented in Table 28, "Community Map History." A description of each of the column headings and the source of the date is also listed below.

- *Community Name* includes communities falling within the geographic area shown on the FIRM, including those that fall on the boundary line, nonparticipating communities, and communities with maps that have been rescinded. Communities with No Special Flood Hazards are indicated by a footnote. If all maps (FHBM, FBFM, and FIRM) were rescinded for a community, it is not listed in this table unless SFHAs have been identified in this community.

- *Initial Identification Date (First NFIP Map Published)* is the date of the first NFIP map that identified flood hazards in the community. If the FHBM has been converted to a FIRM, the initial FHBM date is shown. If the community has never been mapped, the upcoming effective date or "pending" (for Preliminary FIS Reports) is shown. If the community is listed in Table 28 but not identified on the map, the community is treated as if it were unmapped.

- *Initial FHBM Effective Date* is the effective date of the first Flood Hazard Boundary Map (FHBM). This date may be the same date as the Initial NFIP Map Date.

- *FHBM Revision Date(s)* is the date(s) that the FHBM was revised, if applicable.

- *Initial FIRM Effective Date* is the date of the first effective FIRM for the community.

- *FIRM Revision Date(s)* is the date(s) the FIRM was revised, if applicable. This is the revised date that is shown on the FIRM panel, if applicable. As countywide studies are completed or revised, each community listed should have its FIRM dates updated accordingly to reflect the date of the countywide study. Once the FIRMs exist in countywide format, as Physical Map Revisions (PMR) of FIRM panels within the county are completed, the FIRM Revision Dates in the table for each community affected by the PMR are updated with the date of the PMR, even if the PMR did not revise all the panels within that community.

The initial effective date for the Ventura County FIRMs in countywide format was 01/20/2010.

**Table 28: Community Map History**

| Community Name | Initial Identification Date | Initial FHBM Effective Date | FHBM Revision Date(s) | Initial FIRM Effective Date | FIRM Revision Date(s) |
|---|---|---|---|---|---|
| Camarillo, City of | 09/30/1972 | 09/30/1972 | 10/24/1975 | 09/29/1986 | 01/07/2015<br>09/26/2014<br>01/20/2010<br>09/29/1986 |
| Fillmore, City of | 01/23/1974 | 01/23/1974 | 12/19/1975 | 10/17/1978 | 09/26/2014<br>01/20/2010<br>02/01/1984<br>05/19/1981 |
| Moorpark, City of | 09/29/1986 | N/A | N/A | 09/29/1986 | 09/26/2014<br>01/20/2010<br>09/29/1986 |

**Table 28: Community Map History, continued**

| Community Name | Initial Identification Date | Initial FHBM Effective Date | FHBM Revision Date(s) | Initial FIRM Effective Date | FIRM Revision Date(s) |
|---|---|---|---|---|---|
| Ojai, City of | 05/03/1974 | 05/03/1974 | 11/28/1975 | 10/17/1978 | 09/26/2014<br>01/20/2010<br>04/19/1983 |
| Oxnard, City of | 08/09/1974 | 08/09/1974 | N/A | 03/01/1979 | TBD<br>09/26/2014<br>01/20/2010<br>10/15/1985 |
| Port Hueneme, City of | 07/28/1972 | 07/28/1972 | 10/03/1975 | 09/24/1984 | TBD<br>09/26/2014<br>01/20/2010 |
| San Buenaventura, City of | 05/31/1974 | 05/31/1974 | 12/19/1975 | 09/29/1986 | TBD<br>09/26/2014<br>01/20/2010<br>08/19/1987 |
| Santa Paula, City of | 05/24/1974 | 05/24/1974 | 07/25/1976 | 04/15/1980 | 09/26/2014<br>01/20/2010<br>09/03/1997<br>09/18/1985 |
| Simi Valley, City of | 05/17/1974 | 05/17/1974 | N/A | 09/27/1991 | 09/26/2014<br>01/20/2010<br>09/03/1997 |
| Thousand Oaks, City of | 06/07/1974 | 06/07/1974 | N/A | 09/29/1978 | 09/26/2014<br>01/20/2010<br>01/03/1983 |
| Ventura County, Unincorporated Areas | 01/31/1975 | 01/31/1975 | 10/18/1977 | 10/31/1985 | TBD<br>01/07/2015<br>09/26/2014<br>01/20/2010<br>09/03/1997<br>09/28/1990<br>01/05/1989 |

# SECTION 7.0 – CONTRACTED STUDIES AND COMMUNITY COORDINATION

## 7.1 Contracted Studies

Table 29 provides a summary of the contracted studies, by flooding source, that are included in this FIS Report.

**Table 29: Summary of Contracted Studies Included in this FIS Report**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Adams Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Santa Paula, City of; Ventura County, Unincorporated Areas |
| Alamos Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Simi Valley, City of; Ventura County, Unincorporated Areas |
| Arroyo Colorado | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Arroyo Conejo | 03/01/1978 | U.S. Department of Agriculture, Soil Conservation Service | IAA-H-16-72 | January 1976 | Thousand Oaks, City of; Ventura County, Unincorporated Areas |
| Arroyo Las Posas | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Arroyo Santa Rosa and Tributary | 01/20/2010 | Nolte Associates, Inc. | EMS-2000-CO-0057 | September 2004; Revised May 2008 | Thousand Oaks, City of; Ventura County, Unincorporated Areas |
| Arroyo Simi | 09/03/1997 | Schaaf & Wheeler | 92-C4042 | June 1995 | Simi Valley, City of |
| Arundell Barranca | 09/29/1986 | PRC Toups | H-4032 | May 1983 | San Buenaventura, City of; Ventura County, Unincorporated Areas |
| Auto Center Drain | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Balcom Canyon Wash | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Barbara Drive Drain | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Bardsdale Ditch | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Basolo Ditch | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Bear Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Beardsley Wash | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Camarillo, City of; Ventura County, Unincorporated Areas |
| Bell Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Big Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Big Mountain Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Simi Valley, City of |
| Big Sycamore Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Big Sycamore Canyon Tributary | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Blanchard Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Boosey Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Boulder Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Brea Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Simi Valley, City of; Ventura County, Unincorporated Areas |
| Brown Barranca | 09/29/1986 | PRC Toups | H-4032 | May 1983 | San Buenaventura, City of; Ventura County, Unincorporated Areas |
| Bus Canyon Drain | 09/03/1997 | Schaaf & Wheeler | 92-C4042 | June 1995 | Simi Valley, City of |
| Bus Canyon Drain Tributary | 09/03/1997 | Schaaf & Wheeler | 92-C4042 | June 1995 | Simi Valley, City of |
| Calleguas Creek | 01/20/2010 | Kasraie Consulting | * | October 2008 | Camarillo, City of |
| Camarillo Hills Drain | 01/07/2015 | BakerAECOM | Case No. 11-09-3535P | February 2011 | Camarillo, City of |
| Canada De Aliso | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Canada Larga | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Chivo Canyon | 09/03/1997 | Schaaf & Wheeler | 92-C4042 | June 1995 | Simi Valley, City of; Ventura County, Unincorporated Areas |
| Conejo Creek | 01/20/2010 | Nolte Associates, Inc. | EMS-2000-CO-0057 | September 2004 | Camarillo, City of; Thousand Oaks, City of; Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Conejo Mountain Creek | 03/01/1978 | U.S. Department of Agriculture, Soil Conservation Service | IAA-H-16-72 | January 1976 | Thousand Oaks, City of |
| Conejo Park Creek | 09/29/1986 | PRC Toups | H-4032 | July 1983 | Ventura County, Unincorporated Areas |
| Cooper Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Coyote Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Coyote Canyon Wash | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Coyote Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Cozy Del Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Donlon Drain | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Doris Avenue Drain | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Dron Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Dry Canyon Creek | 09/03/1997 | Schaaf & Wheeler | 92-C4042 | June 1995 | Simi Valley, City of |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Dry Canyon Tributary | 09/03/1997 | Schaaf & Wheeler | 92-C4042 | June 1995 | Simi Valley, City of |
| E Street Drain | 10/15/1985 | USACE | IAA-H-1974; IAA-H-1675 Order Nos. 13 and 17 | March 1977 | Oxnard, City of; Ventura County, Unincorporated Areas |
| East Camarillo Drain | 01/07/2015 | BakerAECOM | Case No. 11-09-3535P | February 2011 | Camarillo, City of |
| East Camarillo Drain Tributary | 01/07/2015 | BakerAECOM | Case No. 11-09-3535P | February 2011 | Camarillo, City of |
| East Fork Honda Barranca | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| East Fork Lord Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| East Fork Tripas Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| East Las Virgenes Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| East Las Virgenes Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| East Tributary | 09/03/1997 | Schaaf & Wheeler | 92-C4042 | June 1995 | Simi Valley, City of |
| East Tributary Meier Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| East Tributary Somis Drain | 01/07/2015 | BakerAECOM | Case No. 11-09-3535P | February 2011 | Camarillo, City of |
| Edgemore Drain | 01/07/2015 | BakerAECOM | Case No. 11-09-3535P | February 2011 | Camarillo, City of |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Edwards Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Ellsworth Barranca | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Erringer Drain | 09/03/1997 | Schaaf & Wheeler | 92-C4042 | June 1995 | Simi Valley, City of |
| Eureka Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Fagan Canyon | 09/03/1997 | USACE | General Reevaluation Report | March 1995 | Santa Paula, City of; Ventura County, Unincorporated Areas |
| Fairview Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Fox Barranca | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Fox Canyon Storm Drain | 04/02/1978 | Harris-Toups Associates | H-4032 | July 1977 | Ojai, City of |
| Franklin Barranca | 09/29/1986 | PRC Toups | H-4032 | May 1983 | San Buenaventura, City of; Ventura County, Unincorporated Areas |
| Frey Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Gabbert Canyon Creek | 09/29/1986 | PRC Toups | H-4032 | July 1983 | Moorpark, City of |
| Gill Barranca | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Gillibrand Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Simi Valley, City of; Ventura County, Unincorporated Areas |
| Guadalasca Road Drain | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Haines Barranca | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Hammond Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Happy Camp Canyon Creek | 09/29/1986 | PRC Toups | H-4032 | July 1983 | Moorpark, City of; Ventura County, Unincorporated Areas |
| Happy Camp Canyon Tributary | 09/29/1986 | PRC Toups | H-4032 | July 1983 | Ventura County, Unincorporated Areas |
| Happy Valley Drain | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Happy Valley Drain South | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Harmon Barranca | 09/29/1986 | PRC Toups | H-4032 | May 1983 | San Buenaventura, City of; Ventura County, Unincorporated Areas |
| Hidden Valley Wash | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Hill Canyon | 03/01/1978 | U.S. Department of Agriculture, Soil Conservation Service | IAA-H-16-72 | January 1976 | Thousand Oaks, City of |
| Hilltop Lane Drain | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Holser Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Honda Barranca | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Honda Barranca Tributary | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Hoper Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Hummingbird Creek | 09/03/1997 | Ensign and Buckley Consulting Engineers | EMW-90C-9133 | March 1993 | Simi Valley, City of |
| Hummingbird Creek Tributary | 09/03/1997 | Ensign and Buckley Consulting Engineers | EMW-90C-9133 | March 1993 | Simi Valley, City of |
| Hunt Wash | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| J Street Drain | 10/15/1985 | USACE | IAA-H-1974; IAA-H-1675; Order Nos. 13 and 17 | March 1977 | Oxnard, City of; Port Hueneme, City of |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Javon Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Jepson Wash | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Kenny Grove Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Koenigstein Road Wash | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| La Jolla Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Lake Eleanor Creek | 03/01/1978 | U.S. Department of Agriculture, Soil Conservation Service | IAA-H-16-72 | January 1976 | Thousand Oaks, City of |
| Lake Piru | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Lake Sherwood | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Lang Creek | 01/20/2010 | Nolte Associates, Inc. | EMS-2000-CO-0057 Order No. T005 | September 2004 | Thousand Oaks, City of |
| Las Llajas Canyon Channel | 09/03/1997 | Schaaf & Wheeler | 92-C402 | June 1995 | Simi Valley, City of; Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Las Posas Estates Drain | 09/29/1986 | PRC Toups | H-4032 | May 1983 | Camarillo, City of; Ventura County, Unincorporated Areas |
| Las Sauces Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Las Virgenes Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Las Virgenes Canyon Tributary | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Laskey Mesa West | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Lime Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Lindero Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Lion Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Little Happy Camp Canyon | 09/29/1986 | PRC Toups | H-4032 | July 1983 | Ventura County, Unincorporated Areas |
| Little Happy Camp Canyon Tributary | 09/29/1986 | PRC Toups | H-4032 | July 1983 | Ventura County, Unincorporated Areas |
| Little Sycamore Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Long Canyon Creek | 01/20/2010 | Nolte Associates, Inc. | EMS-2000-CO-0057 | September 2004 | Ventura County, Unincorporated Areas |
| Long Grade Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Madranio Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Magnolia Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Mahan Barranca | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Maxy Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| McNell Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | 1988 | Ojai, City of; Ventura County, Unincorporated Areas |
| Medea Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Meier Canyon Creek | 09/03/1997 | Aqua Resources Incorporated | EMW-89-C-2844 | July 1990 | Simi Valley, City of; Ventura County, Unincorporated Areas |
| Mira Monte Drain | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Mission Drain | 01/07/2015 | BakerAECOM | Case No. 11-09-3535P | February 2011 | Camarillo, City of |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Moon Ditch | 09/29/1986 | PRC Toups | H-4032 | May 1983 | San Buenaventura, City of; Ventura County, Unincorporated Areas |
| Moore Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Mud Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| North Fork Canada De Los Alamos | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| North Ramona Place Drain | 09/29/1986 | PRC Toups | H-4032 | July 1983 | Ventura County, Unincorporated Areas |
| North Simi Drain | 09/03/1997 | Schaaf & Wheeler | 92-C4042 | June 1995 | Simi Valley, City of |
| Nyland Drain | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Oak Canyon Creek | 09/03/1997 | Aqua Resources Incorporated | EMW-89-C-2844 | July 1990 | Simi Valley, City of |
| Oak Canyon Creek (North) | 09/03/1997 | Aqua Resources Incorporated | EMW-89-C-2844 | July 1990 | Simi Valley, City of |
| Oak Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Oak View Drain | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Oleary Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Orcutt Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Oxnard West Drain | 10/15/1985 | USACE | IAA-H-1974; IAA-H-1675; Order Nos. 13 and 17 | March 1977 | Port Hueneme, City of |
| Pacific Ocean | TBD | BakerAECOM | HSFEHQ-09-D-0368 | November 2015 | San Buenaventura, City of; Oxnard, City of; Port Hueneme, City of; Ventura County, Unincorporated Areas |
| Padre Juan Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Palo Comado Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Paso Flores Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Peach Hill Wash | 01/20/2010 | Nolte Associates, Inc. | EMS-2000-CO-0057 | September 2004; Revised May 2008 | Moorpark, City of; Ventura County, Unincorporated Areas |
| Piedra Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Piru Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Pole Creek | 04/17/1978 | Harris-Toups Associates | H-4032 | June 1977 | Fillmore, City of; Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Ponderosa Drain | 01/07/2015 | BakerAECOM | Case No. 11-09-3535P | February 2011 | Camarillo, City of |
| Poplin Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Poplin Creek Tributary | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Puerta Zuela Barranca | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Punte Gorda Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Real Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Reasoner Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Reeves Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Reeves Creek Tributary | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Reimer Ditch | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Revolon Slough | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Rincon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Runckle Canyon | 09/03/1997 | Aqua Resources Incorporated | EMW-89-C-2844 | July 1990 | Simi Valley, City of; Ventura County, Unincorporated Areas |
| Salt Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| San Antonio Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ojai, City of; Ventura County, Unincorporated Areas |
| Sand Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Santa Ana Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Santa Ana Creek Tributary | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Santa Clara River | 01/01/1984 | PRC Toups | H-4032 | 1983 | Santa Paula, City of |
| Santa Clara River Breakout | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Oxnard, City of; Ventura County, Unincorporated Areas |
| Santa Felicia Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Santa Felicia Spillway | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Santa Paula Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Santa Paula, City of; Ventura County, Unincorporated Areas |
| Santa Paula Creek | 01/01/1984 | PRC Toups | H-4032 | 1983 | Santa Paula, City of |
| Santa Rosa East Tributary | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Serrano Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Sespe Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Shekell Road Drain | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Sherwood Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Shields Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Sisar Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Smith Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Solano Verde Wash | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Somis Drain | 01/07/2015 | BakerAECOM | Case No. 11-09-3535P | February 2011 | Camarillo, City of |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| South Branch Arroyo Conejo | 03/01/1978 | U.S. Department of Agriculture, Soil Conservation Service | IAA-H-16-72 | January 1976 | Thousand Oaks, City of; Ventura County, Unincorporated Areas |
| South Fork Canada De Los Alamos | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| South Grimes Canyon Wash | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Moorpark, City of; Ventura County, Unincorporated Areas |
| South Grimes Canyon Wash (North) | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| South Grimes Canyon Wash Tributary | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Stewart Canyon Creek | 04/02/1978 | Harris-Toups Associates | H-4032 | July 1977 | Ojai, City of; Ventura County, Unincorporated Areas |
| Sulphur Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Sycamore Canyon | 09/03/1997 | Aqua Resources Incorporated | EMW-89-C-2844 | July 1990 | Simi Valley, City of |
| Sycamore Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Tapo Canyon Channel | 09/03/1997 | Schaaf & Wheeler | 92-C4042 | June 1995 | Simi Valley, City of; Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Tapo Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Simi Valley, City of; Ventura County, Unincorporated Areas |
| Tapo Canyon Creek (North) | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Tapo Canyon Tributary | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Simi Valley, City of; Ventura County, Unincorporated Areas |
| Thacher Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ojai, City of; Ventura County, Unincorporated Areas |
| Thousand Oaks North Drain | 01/20/2010 | Nolte Associates, Inc. | EMS-2000-CO-0057 | September 2004 | Thousand Oaks, City of |
| Tierra Rejada Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Timber Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Todd Barranca | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Torey Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Tripas Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Tripas Canyon Tributary | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| Valley Road Wash | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Ventura River | 09/29/1986 | Dames & Moore | C-0970 | 1984 | San Buenaventura, City of; Ventura County, Unincorporated Areas |
| Walnut Canyon Drain | 01/20/2010 | Nolte Associates, Inc. | EMS-2000-CO-0057 | September 2004 | Moorpark, City of; Ventura County, Unincorporated Areas |
| Warring Canyon Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Warring Wash | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| West Camarillo Hills Drain Tributary | 01/07/2015 | BakerAECOM | Case No. 11-09-3535P | February 2011 | Camarillo, City of |
| West Fifth Street Drain | 10/15/1985 | USACE | IAA-H-1974; IAA-H-1675, Order Nos. 13 and 17 | March 1977 | Oxnard, City of; Ventura County, Unincorporated Areas |
| West Fork Medea Creek | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| West Fork Orcutt Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| West Fork Salt Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| West Fork Salt Canyon Tributary | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |

**Table 29: Summary of Contracted Studies Included in this FIS Report, continued**

| Flooding Source | FIS Report Dated | Contractor | Number | Work Completed Date | Affected Communities |
|---|---|---|---|---|---|
| West Tributary Long Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| West Wooley Drain | 10/15/1985 | USACE | IAA-H-1974; IAA-H-1675, Order Nos. 13 and 17 | March 1977 | Port Hueneme, City of |
| White Oak Creek | 09/03/1997 | Ensign and Buckley Consulting Engineers | EMW-90C-9133 | March 1993 | Simi Valley, City of |
| White Oak Tributary | 09/03/1997 | Ensign and Buckley Consulting Engineers | EMW-90C-9133 | March 1993 | Simi Valley, City of |
| Windmill Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Wood Canyon | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |
| Wood Ranch Reservoir | 09/28/1990 | DMA Consulting Engineers, Inc. | EMW-86-C-2227 | January 1988 | Ventura County, Unincorporated Areas |

*Data not available

## 7.2 Community Meetings

The dates of the community meetings held for this Flood Risk Project and previous Flood Risk Projects are shown in Table 30. These meetings may have previously been referred to by a variety of names (Community Coordination Officer (CCO), Scoping, Discovery, etc.), but all meetings represent opportunities for FEMA, community officials, study contractors, and other invited guests to discuss the planning for and results of the project.

**Table 30: Community Meetings**

| Community | FIS Report Dated | Date of Meeting | Meeting Type | Attended By |
|---|---|---|---|---|
| Camarillo, City of | 01/2015 | 04/29/2010 | Initial CCO | District Representative and District Chief of Staff for Congress, representatives of FEMA, the USACE, BakerAECOM, LLC and community officials |
| | | 08/28/2013 | Final CCO | FEMA Region IX representatives, and representatives for City of Camarillo |
| Fillmore, City of | 01/20/2010 | 07/29/2004 | Initial CCO | FEMA, the community, and the study contractor |
| | | 09/21/2005 | Final CCO | FEMA, the community, and the study contractor |
| Moorpark, City of | 01/20/2010 | 07/29/2004 | Initial CCO | FEMA, the community, and the study contractor |
| | | 09/21/2005 | Final CCO | FEMA, the community, and the study contractor |
| Ojai, City of | 09/26/2014 | 11/10/2010 | Initial CCO | FEMA, the community, and the study contractor |
| | | 05/22/2013 | Final CCO | FEMA, the community, and the study contractor |
| Oxnard, City of | TBD | 10/26/2015 | Initial CCO | FEMA, the community, US Navy, Kasraie Consulting, NextGen, Rincon Consultants, and BakerAECOM |
| | | TBD | Final CCO | TBD |
| Port Hueneme, City of | TBD | 10/26/2015 | Initial CCO | FEMA, the community, US Navy, Kasraie Consulting, NextGen, Rincon Consultants, and BakerAECOM |
| | | TBD | Final CCO | TBD |
| San Buenaventura, City of | TBD | 10/26/2015 | Initial CCO | FEMA, US Navy, Kasraie Consulting, NextGen, Rincon Consultants, and BakerAECOM |
| | | TBD | Final CCO | TBD |
| Santa Paula, City of | 01/20/2010 | 07/29/2004 | Initial CCO | FEMA, the community, and the study contractor |
| | | 09/21/2005 | Final CCO | FEMA, the community, and the study contractor |

**Table 30: Community Meetings, continued**

| Community | FIS Report Dated | Date of Meeting | Meeting Type | Attended By |
|---|---|---|---|---|
| Simi Valley, City of | 01/20/2010 | 07/29/2004 | Initial CCO | FEMA, the community, and the study contractor |
| | | 09/21/2005 | Final CCO | FEMA, the community, and the study contractor |
| Thousand Oaks, City of | 01/20/2010 | 07/29/2004 | Initial CCO | FEMA, the community, and the study contractor |
| | | 09/21/2005<br>01/11/2008 | Final CCO | FEMA, the community, and the study contractor |
| Ventura County, Unincorporated Areas | TBD | 10/26/2015 | Initial CCO | FEMA, Ventura County, US Navy, Kasraie Consulting, NextGen, Rincon Consultants, and BakerAECOM |
| | | TBD | Final CCO | TBD |

## SECTION 8.0 – ADDITIONAL INFORMATION

Information concerning the pertinent data used in the preparation of this FIS Report can be obtained by submitting an order with any required payment to the FEMA Engineering Library. For more information on this process, see www.fema.gov.

The additional data that was used for this project includes the FIS Report and FIRM that were previously prepared for Ventura County, California.

Table 31 is a list of the locations where FIRMs for Ventura County can be viewed. Please note that the maps at these locations are for reference only and are not for distribution. Also, please note that only the maps for the community listed in the table are available at that particular repository. A user may need to visit another repository to view maps from an adjacent community.

**Table 31: Map Repositories**

| Community | Address | City | State | Zip Code |
|---|---|---|---|---|
| Camarillo, City of | Public Works Department<br>601 Carmen Drive | Camarillo | CA | 93010 |
| Fillmore, City of | City Hall<br>250 Central Avenue | Fillmore | CA | 93015 |
| Moorpark, City of | City Hall<br>799 Moorpark Avenue | Moorpark | CA | 93021 |
| Ojai, City of | City of Ojai Public Works Department<br>401 South Ventura Street | Ojai | CA | 93024 |
| Oxnard, City of | City of Oxnard Planning Department<br>214 South C Street | Oxnard | CA | 93030 |
| Port Hueneme, City of | City of Port Hueneme Public Works Department<br>250 North Ventura Road | Port Hueneme | CA | 93041 |
| San Buenaventura, City of | San Buenaventura City Hall<br>501 Poli Street | Ventura | CA | 93001 |
| Santa Paula, City of | City Hall<br>970 Ventura Street | Santa Paula | CA | 93060 |
| Simi Valley, City of | City Hall<br>2929 Tapo Canyon Road | Simi Valley | CA | 93063 |
| Thousand Oaks, City of | Public Works Department<br>2100 Thousand Oaks Boulevard | Thousand Oaks | CA | 91362 |

**Table 31: Map Repositories, continued**

| Community | Address | City | State | Zip Code |
|---|---|---|---|---|
| Ventura County, Unincorporated Areas | Ventura County Hall of Administration<br>800 South Victoria Avenue | Ventura | CA | 93009 |

The National Flood Hazard Layer (NFHL) dataset is a compilation of effective FIRM databases and LOMCs. Together they create a GIS data layer for a State or Territory. The NFHL is updated as studies become effective and extracts are made available to the public monthly. NFHL data can be viewed or ordered from the website shown in Table 32.

Table 32 contains useful contact information regarding the FIS Report, the FIRM, and other relevant flood hazard and GIS data. In addition, information about the State NFIP Coordinator and GIS Coordinator is shown in this table. At the request of FEMA, each Governor has designated an agency of State or territorial government to coordinate that State's or territory's NFIP activities. These agencies often assist communities in developing and adopting necessary floodplain management measures. State GIS Coordinators are knowledgeable about the availability and location of State and local GIS data in their state.

**Table 32: Additional Information**

| FEMA and the NFIP | |
|---|---|
| FEMA and FEMA Engineering Library website | www.fema.gov/national-flood-insurance-program-flood-hazard-mapping/engineering-library |
| NFIP website | www.fema.gov/national-flood-insurance-program |
| NFHL Dataset | msc.fema.gov |
| FEMA Region IX | FEMA Region IX, 1111 Broadway, Suite 1200, Oakland, CA 94607<br>(510) 627-7181 |
| **Other Federal Agencies** | |
| USGS website | www.usgs.gov |
| Hydraulic Engineering Center website | www.hec.usace.army.mil |
| **State Agencies and Organizations** | |
| State NFIP Coordinator | James Eto<br>California Department of Water Resources<br>3464 El Camino Avenue, Suite 200<br>Sacramento, CA 95821<br>916-574-1409<br>jeto@water.ca.gov |
| State GIS Coordinator | David Harris, Agency Information Coordinator<br>California Resources Agency<br>1416 Ninth Street, Room 1311<br>Sacramento, CA 95814<br>Phone: 916-445-5088<br>david.harris@resources.ca.gov |

## SECTION 9.0 – BIBLIOGRAPHY AND REFERENCES

Table 33 includes sources used in the preparation of and cited in this FIS Report as well as additional studies that have been conducted in the study area.

**Table 33: Bibliography and References**

| Citation in this FIS | Publisher/ Issuer | *Publication Title,* "Article," Volume, Number, etc. | Author/Editor | Place of Publication | Publication Date/ Date of Issuance | Link |
|---|---|---|---|---|---|---|
| Aerial Topographic Maps, 1987 | | *Topographic Map, Rincon Creek, Scale 1:4,800, Contour Interval 4 feet.* | | | February 26, 1987 | |
| City of Simi Valley, 1987 | | *Photo Maps, Scale 1:1,200* | | Simi Valley, California | March 31, 1987 | |
| Daily Free Press, 1907 | Daily Free Press | *High Seas Wreck Ventura Wharf* | | | December 1907 | |
| David R. Dawdy, 1979 | | *"Flood Frequency Estimates on Alluvial Fans," Journal of the Hydraulics Division ASCE, Proceedings, Vol. 105, No. HY11* | David R. Dawdy | | 1979 | |
| Kasraie Consulting | Kasraie Consulting | *Floodplain Map Revision, City of Camarillo, California* | | | November 2007 | |
| MAPIX | Federal Emergency Management Agency | *Flood Insurance Restudy, Santa Clara River and Tributaries, Ventura County, California* | Mainland Joint Venture of Airborne 1, Dewberry, Schaaf and Wheeler, TerraPoint, and URS | | May 2008 | |
| Martha J. Shaw, 1980 | Scripps Institute of Oceanography | *Artificial Sediment Transport and Structures in Coastal Southern California* | Martha J. Shaw | | December 1980 | |
| Nolte Associates, Inc. | Federal Emergency Management Agency | *Ventura County Flood Insurance Study* | | | September 2004 | FEMA Flood Map Service Center msc.fema.gov |

**Table 33: Bibliography and References, continued**

| Citation in this FIS | Publisher/ Issuer | *Publication Title,* "Article," Volume, Number, etc. | Author/Editor | Place of Publication | Publication Date/ Date of Issuance | Link |
|---|---|---|---|---|---|---|
| Oxnard, California 1967, 1968 | City of Oxnard | *Topographic Maps, Scale 1:4,800, Contour Interval 10 feet* | | Oxnard, California | 1967, 1968 | |
| OWI, 2009 | Oceanweather Inc. | *California Pacific Coastal Studies (Southern Coastal Counties): High Resolution Deep Water Wave Climate Forcing Development 1960-2009* | Oceanweather Inc. | | 2009 | |
| PRC Toups | PRC Toups | *Santa Clara River Diversion Structure Engineering Report* | | | August 1978 | |
| SIO, 2014 | Scripps Institute of Oceanography | *California Open Pacific Coast: Southern California Shallow Water Wave Climates SHELF Model Hindcast. California Coastal Analysis and Mapping Project: Open Pacific Coast Phase II* | SIO | | 2014 | |
| State of California, 1980 | State of California, Department of Boating and Waterways | *Summary Report of man's Impact on the California Coastal Zone* | Dr. Douglas L. Inman | | June 1980 | |
| Steve Howe, 1978 | California Tomorrow Environmental Intern Program, California Coastal Commission | *Wind Damage Along the California Coast, Winter 1977-78* | Steve Howe | | December, 1978 | |

**Table 33: Bibliography and References, continued**

| Citation in this FIS | Publisher/ Issuer | *Publication Title,* "Article," Volume, Number, etc. | Author/Editor | Place of Publication | Publication Date/ Date of Issuance | Link |
|---|---|---|---|---|---|---|
| USACE, 1969 | U.S. Army Corps of Engineers, Los Angeles District | *Appendix C: Report on Floods of January and February 1969 in Ventura County* | | | 1969 | |
| USACE, 1970 | U.S. Army Corps of Engineers | *Hydrology for Floodplain Information Studies, Ventura River, Ventura County, California* | | | December 1970 | |
| USACE, 1971 | U.S. Army Corps of Engineers, South Pacific Division | *National Shoreline Study: California Regional Inventory* | | | August 1971 | |
| USACE, 1972 | U.S. Army Corps of Engineers, Hydrologic Engineering Center | *HEC-2 Water-Surface Profiles, Generalized Computer Program, Users Manual* | | | February 1972 | |
| USACE, 1973 | U.S. Army Corps of Engineers, Los Angeles District | *Floodplain Information, San Antonio Creek and Tributaries, Vicinity of Ojai, California* | | | June 1973 | |
| USACE, 1978 | U.S. Army Corps of Engineers, San Francisco and Los Angeles Districts | *Winter Storm Damage Along the California Coast 1977-1978* | George W. Domurat | | 1978 | |
| USACE, 1980 | U.S. Army Corps of Engineers, Los Angeles District | *Ventura County, California: Survey Report for Beach Erosion Control* | | | May 1980 | |

**Table 33: Bibliography and References, continued**

| Citation in this FIS | Publisher/ Issuer | *Publication Title,* "Article," Volume, Number, etc. | Author/Editor | Place of Publication | Publication Date/ Date of Issuance | Link |
|---|---|---|---|---|---|---|
| USACE, 1985 | U.S. Army Corps of Engineers, Los Angeles District | *Cameros Creek Debris/Detention Basin, Goleta, California, Reconnaissance Report, Hydrology, Preliminary* | | | April 1985 | |
| USACE, 1987 | U.S. Army Corps of Engineers, Los Angeles District | *Calleguas Creek Hydrology for Survey Report, Ventura County, California* | | | November 1987 | |
| USACE, April 1973 | U.S. Army Corps of Engineers | *Hydrology for Floodplain Information and Flood Insurance Studies, Santa Clara River and Tributaries, Ventura County, California* | | | April 1973 | |
| USACE, April 1977 | U.S. Army Corps of Engineers | *Regional Flood Frequency Study, Newhall, Saugus and Vicinity, Los Angeles County, Santa Clara River and Tributaries* | | | April 28, 1977 | |
| USACE, August 1977 | U.S. Army Corps of Engineers | *Hydrology for Special Flood Hazard Study, Calleguas Creek and Revolon Slough, Ventura County, California* | | | August 1977 | |
| USACE, February 1977 | U.S. Army Corps of Engineers | *Hydrology for Flood Insurance Studies, City of Santa Paula, Ventura County, California* | | | February 1977 | |
| USACE, June 1977 | U.S. Army Corps of Engineers | *Topographic Map, Santa Paula Creek, Scale 1:2,400, Contour Interval 2 feet* | | | June 1977 | |

**Table 33: Bibliography and References, continued**

| Citation in this FIS | Publisher/ Issuer | *Publication Title,* "Article," Volume, Number, etc. | Author/Editor | Place of Publication | Publication Date/ Date of Issuance | Link |
|---|---|---|---|---|---|---|
| USACE, January 1973 | U.S. Army Corps of Engineers, Hydrologic Engineering Center | *HEC-1 Flood Hydrography Package, Users Manual* | | | January 1973 | |
| USACE, October 1973 | U.S. Army Corps of Engineers, Hydrology Engineering Center | *HEC-2 Water-Surface Profiles, Computer Program 723X6-L202A* | | Davis, California | October 1973 | |
| U.S. Department of the Interior, 1982 | U.S. Department of the Interior, Geological Survey, Hydrology Subcommittee | *Guidelines for Determining Flood Flow Frequency, Bulletin No. 17B* | | | March 1982 | |
| VCDPW, 1967 | Ventura County Department of Public Works | *Topographic Maps, Scale 1:6,000, Contour Interval 20 feet.* | | | 1967 | |
| VCDPW, 1967-1979 | Ventura County Department of Public Works | *Topographic Maps, Scale 1:2,400, Contour Intervals 2 and 5 feet.* | | | 1967-1979 | |
| VCFCD, 1965, et cetera | Ventura County Flood Control District | *Topographic Maps, Scale 1:1,200, Contour Intervals 2 and 5 feet.* | | Fillmore, California | 1965, 1968, and 1971 | |
| VCFCD, 1970 | Ventura County Flood Control District | *Topographic Maps, Scale 1:2,400, Contour Intervals 2 or 5 feet.* | | Oxnard, California | 1970, revised 1975 | |

**Table 33: Bibliography and References, continued**

| Citation in this FIS | Publisher/ Issuer | *Publication Title,* "Article," Volume, Number, etc. | Author/Editor | Place of Publication | Publication Date/ Date of Issuance | Link |
|---|---|---|---|---|---|---|
| VCFCD & VCSMD, 1977 | Ventura County Flood Control District and Ventura County Surveying and Mapping Division | *Topographic Maps, Scale 1:2,400, Contour Interval 2 feet.* | | Ojai, California | 1977 | |
| Ventura County Flood Control District, September 1969 | Ventura County Flood Control District | *The Great Floods of 1969* | | | September 1969 | |
| Ventura County, 1985 | Ventura County, Public Works Agency, Flood Control and Water Resources Department | *Hydrology Manual* | | | Reprinted 1985 | |




# FLOOD PROFILES

ADAMS CANYON

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

01P




# FLOOD PROFILES

ARROYO SANTA ROSA

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

02P




# FLOOD PROFILES

ARROYO SANTA ROSA

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

03P




# FLOOD PROFILES

ARROYO SANTA ROSA

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

04P




FLOOD PROFILES

ARROYO SANTA ROSA

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS




FLOOD PROFILES

ARROYO SANTA ROSA

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

06P

660
655
650
645
640
635
630
625
620
615

ELEVATION IN FEET (NAVD 88)

ROAD

LIMIT OF DETAILED STUDY

S

32000
32500
33000
33500
34000

STREAM DISTANCE IN FEET ABOVE CONFLUENCE WITH CONEJO CREEK

LEGEND

- 0.2% ANNUAL CHANCE FLOOD
- 1% ANNUAL CHANCE FLOOD
- 2% ANNUAL CHANCE FLOOD
- 10% ANNUAL CHANCE FLOOD
- STREAM BED
- CROSS SECTION LOCATION

# FLOOD PROFILES

## ARROYO SANTA ROSA

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

07P




# FLOOD PROFILES

## ARROYO SANTA ROSA TRIBUTARY

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

08P

# FLOOD PROFILES

## ARROYO SANTA ROSA TRIBUTARY

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

09P




# FLOOD PROFILES

## BEARDSLEY WASH

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

10P




FLOOD PROFILES

BEARDSLEY WASH

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS




FLOOD PROFILES

BEARDSLEY WASH

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

12P




FLOOD PROFILES

BELL CANYON CREEK

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

13P




FLOOD PROFILES

BELL CANYON CREEK

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

14P




FLOOD PROFILES

BELL CANYON CREEK

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

15P




FLOOD PROFILES

BROWN BARRANCA

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS

16P




FLOOD PROFILES

BUS CANYON DRAIN

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS




# FLOOD PROFILES

## BUS CANYON DRAIN

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS




# FLOOD PROFILES

BUS CANYON DRAIN

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS




# FLOOD PROFILES

## BUS CANYON DRAIN TRIBUTARY

FEDERAL EMERGENCY MANAGEMENT AGENCY

VENTURA COUNTY, CA

AND INCORPORATED AREAS